

**STATE OF NEW HAMPSHIRE
DEPARTMENT OF TRANSPORTATION**

2006 CAD/D PROCEDURES AND REQUIREMENTS



EFFECTIVE: APRIL 13, 2006

PART I – GENERAL INTRODUCTION..... 1

Disclaimer.....1

Revision Summary.....2

 April 2006.....2

 April 2005.....3

 April 2004.....3

 April 2002.....4

Introduction5

Current Nhdot Software Versions.....6

 Major Software and Current Production Versions.....6

 Future Upgrades6

PART II – MICROSTATION 7

File Naming7

 Cut Sheets.....7

 Roll Plans.....7

Level Assignments and Symbology8

Seed Files9

 Imperial 2D Seed File (NHSEEDF2.DGN).....9

 Imperial 3D Seed File (NHSEEDFT.DGN)9

 Metric 2D Seed File (NHSEEDM2.DGN)9

 Metric 3D Seed File (NHSEEDM.DGN)9

Reference File Attachments10

Directory Structure11

Fonts12

Text Size and Spacing.....13

Text Styles13

Line Styles14

 NHDOT Custom Line Style Resource Files.....14

 Scaled Linestyles.....14

 Custom Linestyle Scaling Charts.....14

 True Size Linestyles15

 Linestyles Created at 1:116

Color Table.....16

Cell Files17

Dimensioning.....18

Cross-Section Drawings18

Bridge Detail Sheets.....19

Plotting19

Pen Tables20

BatchPlot20

PART III – MX 21

File Naming21

Model Naming.....21

String Labeling21

Style Sets.....22

Feature Sets.....22

Drawing Macros23

Cross-Section Settings Files23

Macro Symbols & Lines.....23

PART IV – OTHER PROJECT DATA..... 25

Project Journal Files25

 Project Journal Guidelines.....25

 Sample CAD/D Project Journal.....26

Drawing Quality Assurance / Quality Control.....29

 QA_Input.....29

 QuikChek.....29

 Spot_Fix29

PART V - ENGINEERING CONSULTANT DELIVERABLE REQUIREMENTS 31

Overview.....31

File Format And Delivery31

 Requirements For Submitting Electronic Data To NHDOT31

 Data Submission.....32

 Deviation From Format32

 MicroStation Only Deliverable.....32

 MicroStation Plot Files (Final Design Consultants Only)33

 File Conversion.....33

Exchanging Right-of-Way Data34

NHDOT Design Process	34
Plan Preparation.....	34
Preliminary Design.....	35
Final Design.....	36
Projects Designed Using InRoads.....	36
Specialized Development by Design Consultants	37
NHDOT Resources Available for Consultants.....	37
PART VI - APPENDIX.....	39
Appendix A - MicroStation Drawing Names.....	39
Plan Drawings	39
Cut Sheet Drawing Types.....	40
Bridge Design Detail Drawings.....	41
Appendix B - Level Mapping Convention	43
Appendix C - NHDOT Custom Linestyles & Font	45
Appendix D – MX Model Naming Convention	49
Plan Preparation Models.....	49
Preliminary Design Models	50
Final Design Models.....	50
Appendix E – MX Detail String Labeling Convention (Topical)	51
GENERAL USE:.....	51
BOUNDARIES:	51
ROADWAY FEATURES:	51
BRIDGE FEATURES:	52
RAILROAD FEATURES:	52
STRUCTURES:.....	52
UTILITIES:	52
SIGNING/SIGNALS:.....	53
OTHER GROUND FEATURES:.....	53
CONTOURS:	54
AERIALS:	54
Pit Surveys:.....	56
Text Strings:	56
Appendix F – MX Detail String Labeling Convention (Alphabetical).....	57
Appendix G – MX Design String Labeling Convention	63
Appendix H – MX Data Transfer Formats	65
LandXML.....	65
HALGN.....	65
Sample HALGN Input Data	65
Description of HALGN Format.....	66
VERAT.....	67
Sample VERAT Input Data	67
Description of VERAT Format	67
Appendix I – Construction Reports	69
Sample Alignment Report (COGO Style)	69

Sample Alignment Report (Coordinates)70

Appendix J – Cross Section Set Labels.....71

PART I – GENERAL INTRODUCTION

DISCLAIMER

The procedures described in this document are for reference only. This information is provided on an "as is" basis. The material contained is provided without warranty or liability of any kind to the New Hampshire Department of Transportation (NHDOT).

Updating this manual is intended to be a continuous process. As technology evolves, policies change, and process improvements are discovered, this document will be updated to reflect those changes.

As with any documentation, improvements can and should be made. Any additions, suggestions or comments for improvement are encouraged. This documentation is not meant to be a complete instructional document. The intent is to provide guidelines that, if followed, will result in better quality and consistency for electronic plans and documents. Documentation of NHDOT CAD/D practices and procedures can be found on the Internet at <http://nh.gov/dot/cadd/>.

This manual, in its entirety, may be freely copied and distributed for the purpose of providing a consistent guide to the computer aided design & drafting (CAD/D) requirements of the New Hampshire Department of Transportation. Copies of this manual along with CAD/D resource files (style libraries, naming conventions, etc.) can be downloaded at <http://nh.gov/dot/cadd/cadd.html>.

Any recommendations for improvements to this documentation are welcome. Any errors found should be brought to the attention of the CAD/D Staff so corrections can be made. For additional information or detailed explanations of the standards described within this document, contact:

CAD/D Support and Development
New Hampshire Department of Transportation
PO Box 483
Concord, NH 03302-0483

E-mail: cadd@dot.state.nh.us
Tel: 603-271-2171

REVISION SUMMARY

APRIL 2006

General

- The CAD/D website address has been changed to: <http://nh.gov/dot/cadd/>
- The email address has been changed to cadd@dot.state.nh.us

Part II – MicroStation

- Use of NHDOT-defined MicroStation line styles is required.
- The text style and linestyle sections have been expanded and clarified.
- The lists of drawing names have been expanded and clarified.

Part III – MX

- Aerial survey data has been merged into the EXD style set.

Part V – Engineering Consultant Requirements

- LandXML is now the preferred method of exchanging design data between MX and other design software.
- A process for exchanging right-of-way data has been added.
- File submission requirements for projects designed with InRoads have been updated.

Appendix

- Appendix A has been expanded to include additional drawing information.
- Appendix H has been modified to encourage the use of LandXML when transferring design data between MX and other design software.

APRIL 2005

General

- No significant changes.

Part II – MicroStation

- Added NHDOT website location of engineering detail drawings.
- Update to directory structure for projects containing multiple bridges.
- Added text style information for Bridge Design projects.

Part III – MX

- Style set & feature set listing reformatted to include additional information.

Appendix

- Changes to MicroStation drawing names in Appendix A.
- Linestyle charts have been updated in Appendix C.
- Special characters included in the nh_engineering font (font 180) are listed.
- Appendix D (MX model names) has been updated to reflect current practices.
- MX String label lists have been updated.
- A new section – Appendix J – has been added to document MX Cross Section Sets.

APRIL 2004

General

- No significant changes.

Part II – MicroStation

- References to MicroStation/J features have been modified to reflect the upgrade to MicroStation v8.
- References to Settings Manager have been removed.
- Corrected errors in custom linestyle scaling charts.
- New cell files added. These are identified within the text.

Part III – MX

- Style sets have been updated for MX 2.6/MicroStation v8.

Appendix

- References to MX version 2.5 have been modified to reflect the upgrade to MX 2.6
- Modifications have been made to the MicroStation drawing name list. Specific changes are identified in the drawing list.
- Some MX string labels have been added or modified. These are identified within the string label tables.

APRIL 2002

General

Consultant deliverable specifications relocated from various parts of the document and combined as *PART V - ENGINEERING CONSULTANT DELIVERABLE* Requirements

Part II – MicroStation

- The process for creating cut sheets has been modified along with the sheet naming convention.
- The project directory structure was modified to include subdirectories for front sheets and profiles. The bridge directory now includes additional subdirectories.
- Changes to cell file listing – titles.cel was renamed to stamps.cel, borders.cel, br_borders.cel, stnoffset.cel, and turnrad.cel have been added.
- Information about the NHDOT pen table has been included.
- BatchPlot information has been added.

Part III – MX

- Additional style sets have been listed.

Part IV – Other Project Data

- Information about the quality assurance/quality control software has been included.

Part V – Engineering Consultant Requirements

- New section.
- NHDOT will only accept plan drawings that were developed in MicroStation for projects that were initiated after April 18, 2002.
- MicroStation plot file returnable changed from HPGL to PDF format.

Appendix

- Modifications have been made to the MicroStation drawing name list. Specific changes are identified in the drawing list.
- Information about MicroStation level colors, styles, and cell names have been removed to avoid potential conflicts with documentation on the CAD/D website.
- Some MX string labels have been added or modified. These are identified with the string label tables.

INTRODUCTION

This document contains the New Hampshire Department of Transportation's (NHDOT) specifications for required electronic (computer) data as it relates to engineering design projects. It explains the minimum requirements that must be met for all Computer Aided Design & Drafting (CAD/D) data produced by and for the New Hampshire Department of Transportation. This is to ensure that CAD/D files can be used by the entire project team throughout all phases of project development. While the requirements contained herein provide a basis for uniform CAD/D practice for NHDOT projects, precise rules that would apply to all possible situations that may arise are not possible to describe. Situations may exist where these standards will not apply. If variances from the NHDOT CAD/D Procedures and Requirements are necessary for a project, they must be approved in writing by the NHDOT Project Manager and documented in the Project Journal File as defined herein.

As a minimum, engineering consultants are expected to adhere to the standards that were in force at the time the contract was initiated. Consultants may voluntarily choose to follow a later revision.

In addition to the traditional hardcopy delivery items, NHDOT requires supplementary electronic data delivery items. This data shall be submitted in the formats specified by this document. In general, design data and Digital Terrain Model (DTM) data is to be provided in the MX model file, LandXML, or 3-D DXF file formats, and graphical data is to be provided in MicroStation's .DGN drawing format. Organizations wishing to perform professional engineering services for NHDOT are required to deliver electronic data as specified by this document. This specification also requires organizations to accept and utilize pertinent electronic input data as provided by NHDOT.

These electronic delivery items **DO NOT** replace any **hardcopy** delivery items.

This document is published as an update to the "CAD/D PROCEDURES AND REQUIREMENTS" document dated April 2005 and supersedes all CAD/D standards previously published.

Trademarks

Microsoft, **Windows** and **Windows NT** are registered trademarks of Microsoft Corporation.

MicroStation, **MDL**, **InRoads**, **GEOPAK**, **MX**, and **MXROAD** are registered trademarks of Bentley Systems, Inc.

CURRENT NHDOT SOFTWARE VERSIONS

NHDOT desires to stay current with state of the art trends in the market, however, budget constraints, statewide implementation, impact on users, and providing support for the new features must be considered prior to any change.

As NHDOT makes a change that results in modifying electronic procedures, the *CAD/D Procedures and Requirements* will be updated where necessary to reflect the change. A list of the modifications will be found in the revision summary. **As a rule, until documentation is modified, no deviation from the current dated requirements should be considered.**

MAJOR SOFTWARE AND CURRENT PRODUCTION VERSIONS

1. MicroStation v8 2004 edition (version 08.05.02.35)
2. MX 2004 edition, service pack 2 (version 08.05.02.25)
3. Microsoft Office 2000 products with Excel 2002

FUTURE UPGRADES

As this document is being written, new versions of MicroStation and MX are being prepared for release. The impact, if any, caused by the release of the XM versions of MicroStation and MX is not yet known.

PART II – MICROSTATION

FILE NAMING

An attempt shall be made to have electronic files named using only an eight character file name with a .DGN extension. However, it is understood that this will not always be possible or preferable. Drawing names will only contain alphanumeric characters, "-", and "_". No spaces or special characters shall be used.

CUT SHEETS

Project sheet file names are composed of four parts; the NHDOT state project number (first five characters), drawing type, sheet number (usually the last two characters), and the file extension. The five digit project number is assigned by NHDOT. The letter(s) following the project number indicate the type of cut sheet drawing. The sheet number is a sequential listing of the type of cut sheet for the project. (Ex. 12345R01 : “12345” - project number, “R” – ROW, “01” – ROW Cut Sheet 1.) The extension is always “.DGN”. Modifications to this format will be noted in the Project Journal File. A listing of drawing type designators used by NHDOT is contained in *APPENDIX A - MICROSTATION DRAWING NAMES* beginning on page 39.

Realizing that there are a number of different ways to accomplish this same task, variations to the method described above may be acceptable with prior approval of NHDOT. Consultants wishing to use an alternative method should contact the CAD/D development staff.

ROLL PLANS

Project “roll-plan” file names are composed of three parts; the NHDOT state project number (first five fields), drawing type (last three fields), and the .DGN file extension.

A further explanation of standard naming conventions and drawing type designators used by NHDOT is contained in *APPENDIX A - MICROSTATION DRAWING NAMES* beginning on page 39.

LEVEL ASSIGNMENTS AND SYMBOLOGY

MicroStation v8 allows unlimited levels in each file. The level schemes originally developed for MicroStation/J have been modified to take advantage of the additional levels available in v8.

Elements used to construct CAD/D drawings shall be placed on the appropriate design file levels. The level naming convention can be found on the NHDOT CAD/D website. Standard plan sheet symbol drawings are not maintained by the CAD/D Section. They are available on the NHDOT website (Business Center → Information for Engineers, Contractors & Consultants → Specifications, Standards & Details).

Line weights, styles and text sizes shall conform to the NHDOT level mapping located on the NHDOT CAD/D website. The website address is listed in the Disclaimer section at the beginning of this document. Use of NHDOT-defined MicroStation line styles is required. The consultant, with the approval of the Project Manager, may create symbols that are not covered in the NHDOT Design Manual or contained in NHDOT cell libraries that are needed to complete project plans. Resource files containing any linestyles and/or symbols created by the consultant for use on the project drawings will be provided to NHDOT.

Actual symbols for use with MicroStation software, including standard borders, are contained in NHDOT's standard cell libraries and are available in MicroStation .CEL file format. A standard color table, Imperial and metric line style resource files with NHDOT line styles and font library with NHDOT fonts for use with MicroStation are available. This data is available on the NHDOT website or can be requested through the Project Manager. The website address is listed in the Disclaimer section at the beginning of this document.

Level library files contain level names and color/weight/style information for MicroStation .DGNs. For Highway Design use there are level library files available for most detail drawings. These files have the same 3-character name as the drawing with a .CSV extension. For example, the level naming file for drawing *12345exd.dgn* will be *exd.csv*.

There are two .CSV files to be utilized when creating .DGNs for the Bureau of Bridge Design. The first file is called *brc.csv*, and stands for BRidge Cut-sheet. It contains the names required to accurately place graphical elements on a cut sheet (also referred to as a detail sheet). The second file, called *brd.csv*, contains the names required to place graphical elements in a .DGN at project coordinates. Many of the names in *brd.csv* are required in order to transfer elements to MX from MicroStation.

Level standards for front sheets, right-of-way summaries, and property layout sheets are contained in *borders.csv*. Filters for displaying borders are included in *BorderFilters.dgnlib*. All the level files mentioned are available on the CAD/D website or can be requested through the Project Manager. The website address is listed in the Disclaimer section at the beginning of this document.

SEED FILES


MicroStation uses “seed” files to create all design files. These seed files are templates in which standard parameters are set according to what is needed to begin drafting for a specific type of work in accordance with NHDOT standards. The seed file defines the working units for the file, global origin, view attributes, default color table, text settings, coordinate readout and several other important parameters. NHDOT supplies seed files for both Imperial and metric drawings. Seed files allow the user to begin work in a standard format and maintain uniformity.

By default, NHDOT design teams are working with 2-D drawings. If a consultant prefers to use 3-D drawings, this should be mentioned prior to obtaining survey or design data from the Department.

Two of the most important settings in the seed file are the working units and global origin. Working units are expressed as master units and fractional sub-units. The number of positional units per sub-unit is called the working resolution. The working resolution determines the precision to which elements are drawn. The format for the working units in MicroStation is defined as MU:SU (master units, sub-units).

IMPERIAL 2D SEED FILE (NHSEEDF2.DGN)

Working Units:
 Master Units = ft
 Sub-Units = inches
 Global Origin: X= 500
 Y= 500
 Resolution 254/inch




IMPERIAL 3D SEED FILE (NHSEEDFT.DGN)

Working Units:
 Master Units = ft
 Sub-Units = inches
 Global Origin: X= 500
 Y= 500
 Z= 10,000
 Resolution 254/inch

METRIC 2D SEED FILE (NHSEEDM2.DGN)

Working Units:
 Master Units = m
 Sub-Units = mm
 Global Origin: X= 500
 Y= 500
 Resolution 10000/meter



METRIC 3D SEED FILE (NHSEEDM.DGN)

Working Units:
 Master Units = m
 Sub-Units = mm
 Global Origin: X= 500
 Y= 500
 Z= 10,000
 Resolution 10000/meter

The global origin has been set at 500, 500, 10000 for both metric and Imperial files. Using these coordinates, the seed files can be used for both drawings based at State Plane Coordinates and drawings, such as cross-sections, profiles, typicals and special details, using a local coordinate base. The 10,000 unit offset allows MX data with null elevations to be transferred properly.

To reset the global origin for a drawing file, enter the key-in GO=-500,-500,-10000 and use the right mouse button to issue a "reset" command.

REFERENCE FILE ATTACHMENTS


A reference file is a MicroStation design file attached as a background file to an active design file, thus allowing several design groups to share the same information without the need to copy the file(s). MicroStation can attach a reference file by one of three different ways:

1. Name only – the path to the referenced file is resolved by the MicroStation configuration variable MS_RFDIR.
2. Relative path – the reference file name and its location relative to the master file.
3. URL address – the file is attached in the form of a URL address using relative paths.

In order for a project to be delivered to NHDOT in an electronic format that will allow future use of the files for printing purposes without modification to the files, the reference files must be attached in a way that will allow MicroStation to resolve the reference file attachment paths regardless of the drive or parent directory of the project. Option 1 above is the preferred method for NHDOT projects, since it allows the files to be moved from drive to drive without losing the reference file attachments. However, this option requires the MicroStation configuration variable, MS_RFDIR, be set for all NHDOT projects.

DIRECTORY STRUCTURE

The standard directory structure being used for CAD/D projects within NHDOT is shown below: Directory and file names will only contain alphanumeric characters and underscores ("_"). No spaces will be included in names.



CAD/D files are stored in directories under the *Cadd* folder.

Files that need to be used with MX or by multiple bureaus are stored in the *Prj* folder.

The other folders will contain files that are only pertinent to that particular bureau.

BrD – Bridge Design

Env – Environment

Hwy – Highway Design

Row – Right of Way

Trf – Traffic

The *BrD* folder contains the following subdirectories:

AbutA - Detail plans depicting Abutment A footing, masonry, and reinforcing.

AbutB - Detail plans depicting Abutment B footing, masonry, and reinforcing.

BrSite - General Plan, Site Plan, and boring logs.


Pier - Detail plans depicting Pier footing, masonry, and reinforcing.

PrelPlns - Preliminary Plans. After preliminary plans are accepted, pdf files of the Genplan & Siteplan drawings are created. Other drawings are copied into this directory and renamed.

Super - Superstructure details.

The *CutSheet* folder under *Prj* is where Highway Design's final contract plan DGN files will be stored. Front sheets are stored in the *FrontSheet* folder under *Prj*. Bridge Design contract plan files are stored in the various Bridge directories.

MXData is used to store miscellaneous MX files. The *macros* and *styles* folders (*imperial_macros* and *imperial_styles* on Imperial projects) under *Prj* are created by MX to store project specific macros and style sets.



If there are multiple bridges on a project, the *BrD* directory structure is typically modified so that drawings for each bridge are kept separate. The subdirectories under *BrD* can be named for the feature being crossed or in cases where the same feature is crossed multiple times, the bridge number

FONTS

MicroStation font resource files are binary files created from font cells, TrueType, Postscript, or AutoCAD SHX fonts. MicroStation will read multiple font resource files according to the paths set by the MS_SYMBRSC configuration variable in the selected workspace. However, within MicroStation they are compiled into a list of all the fonts from all the resource files that were found. If one file contains a font with the same number assigned as another font resource file, the user will see the last one located.

The NHDOT font resource files are called *nh-custom-font.rsc* & *nhttfont.rsc*. Any fonts within the NHDOT resource files that are no longer in use will be maintained for backward compatibility purposes. The fonts contained within the NHDOT resource files are described below. Font numbers below 170 are reserved for standard MicroStation fonts.

NH-CUSTOM-FONT.RSC

Font	Description
180	nh_engineering (Engineering w/bridge and drafting symbols) Non-alphanumeric characters contained within this font are pictured in <i>APPENDIX C - NHDOT CUSTOM LINSTYLES & FONT</i> on page 45.

The following information is only included for historical reference. Project drawings should use the Windows true-type fonts instead of the MicroStation fonts listed below.

NHTTFONT.RSC


Font	Description
170	True Type font Arial
171	True Type font Arial Bold
173	True Type font Courier
174	True Type font Courier Bold
176	True Type font Times New Roman
177	True Type font Times New Roman Bold
182	True Type font Comic Sans
183	True Type font Comic Sans Bold

TEXT SIZE AND SPACING

Standard text sizes and fonts have been defined to ensure uniformity and legibility on all CAD/D drawings. The correct text size is shown on the level mapping table and is dependent on the plot scale. Note that the text size listed represents both the text height and width. Since, the most important issue with text is that it should be legible, font and text size may vary if absolutely necessary. Text line spacing varies between half of the text size and the text size depending on the use.

TEXT STYLES

For bridge drawings, text styles are available at various engineering and architectural scales. The styles are located within `nhdotTextStyleLibraryFT.dgnlib` (Imperial) & `nhdotTextStyleLibraryM.dgnlib` (metric). These `dgnlib`'s should be defined by the `MS_DGNLIBLIST` variable. The style names include the intended purpose of the text and the scale of the drawings they will be used on.



<code>nh_eng</code>	Used for note and detail text
<code>Title nh_eng</code>	Used for detail title text
<code>Note Title nh_eng</code>	Used for a smaller or sub-title text

Dimension and text style libraries used by Bridge Design are available on the NHDOT CAD/D website.

LINE STYLES

Line style is part of the symbology of graphical elements in MicroStation. An element can be set to the standard MicroStation line styles (numbered 0 - 7) or to a custom line style defined in a custom line style resource file. Custom line styles are user definable resource files for the display of different patterns, for example, a tree line, fence line, guardrail, etc. When an element is drawn in MicroStation with a custom line style, the definition of the line style is not contained within the design file. The resource file from which it was selected must be packaged with the design file and it must be found by MicroStation's configuration in order to properly display the line. Therefore, users are strongly discouraged from creating their own custom line styles. Use the NHDOT supplied custom line style resources whenever practical. Graphical depictions of NHDOT MicroStation linestyles are shown in *APPENDIX C - NHDOT CUSTOM LINSTYLES & FONT* on page 45.

NHDOT CUSTOM LINE STYLE RESOURCE FILES

Standard NHDOT Custom line style files	
<u>Imperial</u>	<u>Metric</u>
line-ft.rsc	line-m.rsc
pipe-ft.rsc	pipe-m.rsc

As mentioned above, custom line styles are user definable in MicroStation. NHDOT linestyles are created at three different scales depending on the intended use. These settings will be included in the GDM rules files. The GDM programs are described in more detail in *DRAWING QUALITY ASSURANCE / QUALITY CONTROL* on page 29.

Caution must be exercised as the definition for the line style is maintained in a resource file and a design file only contains links to custom line style resource files. If a new (non-standard) custom linestyle is developed by a user, those resource files must be delivered with the project. Users shall not modify the NHDOT delivered standard custom line style files.

SCALED LINSTYLES

Linestyles for plan drawings have been created for use on a 1"=50' scale Imperial (1:500 metric) drawing. This includes most of the linestyles available. When these linestyles are used on 1"=20' Imperial drawings should be scaled by 0.4 and when used on 1:250-scale metric drawings they should be scaled by 0.5. Charts showing scale values for other drawing scales are shown below.

CUSTOM LINSTYLE SCALING CHARTS

Imperial

Scale for plotting	Ratio	Custom linestyle scale setting
1"=1"	1:1	0.0016
6"=1'	1:2	0.003
3"=1'	1:4	0.006
2"=1'	1:6	0.01

1 1/2"=1'	1:8	0.013
1"=1'	1:12	0.02
3/4"=1'	1:16	0.026
1/2"=1'	1:24	0.04
3/8"=1'	1:32	0.053
1/4"=1'	1:48	0.08
3/16"=1'	1:64	0.1066
1/8"=1'	1:96	0.16
1"=10'	1:120	0.2
3/32"=1'	1:128	0.2135
1/16"=1'	1:192	0.32
1"=20'	1:240	0.4
1"=30'	1:360	0.6
1"=50'	1:600	1
1"=100'	1:1200	2

Metric

Scale for plotting	Custom linestyle scale setting
1:1	0.002
1:2	0.004
1:5	0.01
1:10	0.02
1:20	0.04
1:25	0.05
1:50	0.1
1:100	0.2
1:125	0.25
1:250	0.5
1:500	1

TRUE SIZE LINSTYLES

Linestyles that are defined to be a specific size (such as pipe and railroad styles) should always be drawn at a scale of 1. Styles in this group include:

BmGrDbl	DrainPipe	SheetPile
BmGrLt	PCurbLt	TrafBarls
BmGrRt	PCurbRt	UnderDrain
CblGrLt	Pavemark	XPipeE#
CblGrRt	PipeE#	XPipeP#
CurbLt	PipeP#	
CurbRt	Railroad	

The names are the same for both Imperial and metric except the numbers on the pipe linestyles.

LINESTYLES CREATED AT 1:1

The *line-ft.rsc* and *line-m.rsc* files also contain custom line styles created at a scale of 1:1. In order for the arrowheads of these lines to be properly proportioned, the user must enter the scale associated with the plot size of the drawing in the Line Styles dialog box for custom line styles before placing the line. The line styles for which this rule applies include:

ArBegOpn	ArrowBr	LeaderBr
ArBegSld	BreakBr	LedgeBr
ArEndOpn	DimBr	RocklineBr
ArEndSld	GroundBr	

There are multiple ways to alter the scale of linestyles on a drawing. To set the scale, select *Element* → *Line Style* → *Custom*. Select the linestyle, check the "Scale factor" box and enter the desired scale. Click on the graphic representation of the linestyle to implement the change. An alternative way is to issue the key-in *dwg celtscale #* where the # is replaced with the desired scale. Future lines will be drawn at the new scale. To alter the scale of linestyles that have already been drawn, select all the elements to be changed. Issue the *Change Linestyle Scale #* key-in replacing the # with the desired scale.

COLOR TABLE

A standard color table is necessary to provide visual consistency thus allowing users to easily identify elements in shared files and for consistency in color plotting. NHDOT has its own default color table called *nh-color.tbl*. The table defines 256 colors from which an active color can be selected and applied to an element.

CELL FILES

The following graphic cell files have been created for use on NHDOT projects. Items shown in *italics* have been added since the last edition.

borders.cel	cut sheet borders (including front sheets, ROW summary, property layout and xsection borders and their text cells)
br_2bral.cel	2 bar aluminum bridge rail and approach rail details
br_3bral.cel	3 bar aluminum bridge rail and approach rail details
br_bgr.cel	beam guardrail and end section details
br_borders.cel	miscellaneous bridge borders
br_bore.cel	boring sheet symbols
br_brush.cel	2 bar aluminum approach rail with brush curb
br_curb.cel	granite bridge curb, type A & B bituminous curb, & Jersey barrier
br_exrai.cel	existing rail details
br_misc.cel	borders, state seal, state outline, rip-rap, slope lines, waterstops, sheet piles
br_pile.cel	HP sections and Pile Key
br_precast	New England Bulb Tees (precast concrete beams)
br_t2pl2.cel	T2 rail, approach rail, and safety fence details
br_t3pl2.cel	T3 rail and approach rail details
br_t4pl2.cel	T4 rail and approach rail details
br_weld.cel	weld symbols
drainage.cel	proposed drainage detail cells
environ.cel	environmental detail cells
exist-in.cel	existing topography cells
grdrail.cel	proposed guardrail detail cells
legends.cel	hearing plan legends
logos.cel	NHDOT and other logos
notes.cel	project begin/end notes
pavemark.cel	proposed pavement marking detail cells
row.cel	proposed right-of-way detail cells
signals.cel	proposed signalization detail cells
signs.cel	proposed sign detail cells
stamps.cel	miscellaneous roll/plan sheet cells
StnOffset.cel	Station–Offset macro cells
turnrad.cel	Imperial turning radii templates
utility.cel	proposed utility detail cells
xsect.cel	cross-section detail cells



The following pattern cell file has been created for use on NHDOT projects.

nhpatern.cel	hearing plan removal patterns
--------------	-------------------------------

Cells from Bentley's *areapat.cel* and *archpa.cel* may also be used.

DIMENSIONING

Dimensions should appear as shown in the Highway Design Manual with the following exception: The dimensions for Bridge detail drawings shall be placed to have the appearance of those that follow:



The use of Dimension Styles is strongly encouraged for the placement of all dimensions on structural design drawings, since, at a minimum, it will select the proper text size. It is understood that in order to achieve the dimension appearances shown above, the Dimension Style defaults will, at times, need to be overridden.

Dimension style names reflect the scale

Dimension and text style libraries used by the Bureau of Bridge Design are available on the NHDOT CAD/D web site.

CROSS-SECTION DRAWINGS

NHDOT has decided to store MicroStation cross-sections in one or more files each containing a number of cross-sections. This method is compatible with MX and allows for a smaller number of DGN files to be created for the project. The sections are plotted using a batch plot option that plots all instances of an element contained within the border cell.

Realizing that there are a number of different ways to accomplish this same task, variations to the method described above may be acceptable with prior approval. Consultants wishing to use an alternative method should contact the CAD/D development staff.

BRIDGE DETAIL SHEETS

A single detail sheet frequently requires the placement of several details of various scales. To accomplish this, all details shall be drawn at a scale of 1:1 while using the NHDOT standard working units defined within the NHDOT seed files. The detail sheet shall be composed by applying scale factors to the self-referenced attachments of the detail drawing. The border of the detail sheet shall be a cell placed on the drawing at a scale of 1. Detail drawings shall not be created by either increasing the scale of the border or by temporarily adjusting the working units of the file, in any way.

PLOTTING

The plotter driver file (file extension .PLT) is used to set default plotter settings. Style records used within NHDOT .PLT files are taken directly from the Bentley supplied *hpgl2.plt* file. Black and white plot drivers have been modified to force all pen colors to black except pens 10-14 which are defined as various shades of gray in the NHDOT color table. The following lines have been added to black and white plot drivers:

```
;plot colors 1-9,15-254 black  
pen(1)=(1-9,15-254)/rgb(0,0,0)
```

The following lines replaced the lines in the Bentley supplied plot drivers:

```
; units for weight stroke are multiples of .025 mm  
weight_strokes=(3,8,13,18,25,30,35,40,45,50,55,60,65,70,75,80,85,90,95,100,105,110,115,120,125,130,135,140,145,150,155,160)  
largest_polygon=2048
```

Plotter driver files should be edited for plotter specific adjustments only. Changes intended to affect all plots should be done in the pen tables.

PEN TABLES

A pen table is used to alter the way a drawing is sent to the plotter. It can be used to control the levels that are plotted, control the order in which they are plotted, make text substitutions, or run macros at plot time. NHDOT uses a pen table called nhdot-pen.tbl to make a number of text substitutions in plan borders and front sheets. The variables that are substituted are typically defined in the project control file (pcf). Currently defined substitutions include:

Drawing text	Text substitution	Description
\$PROJCLASS\$	\$(PROJCLASS)	Project class
\$STNO\$	\$(STNO)	State project number
\$SCALE\$	\$(NH_SCALE)	Project scale
\$FEDNO\$	\$(FEDNO)	Federal project number
\$NHPROJ\$	\$(NHPROJ)	"N.H. PROJECT NO. 12345"
\$ROUTENOS\$	\$(ROUTENO)	Route number or road name
\$RSHTOTS\$	\$(RSHTOT)	Total number of right-of-way plan sheets
\$WSHTOTS\$	\$(WSHTOT)	Total number of wetlands sheets
\$CSHTOTS\$	\$(CSHTOT)	Total number of construction plan sheets
\$MRSHTOTS\$	\$(MRSHTOT)	Total number of Materials & Research plan sheets
\$BT\$	\$(BT)	Total number of bridge sheets
\$PBT\$	\$(PBT)	Total number of preliminary bridge sheets
\$BRNO\$	\$(BRNO)	Bridge inventory number
\$BRDESCR\$	\$(BRDESCR)	Bridge description (road over feature crossed)
\$BRFILNO\$	\$(BRFILNO)	Bridge file number
\$BRDIR\$	\$(lastdirpiece(_DGNFILE))	
\$TIMES\$	_TIME_	Current time
\$FILES\$	_FILE_	DGN file name
\$USERS\$	\$(_USTN_USERNAME)	User name
\$DATES\$	_DATE_	Current date
\$FILENAME\$	\$(basename(_DGNFILE))	DGN file name without directory path
\$ROWTOWNS\$	\$(ROWTOWN)	"TOWN OF -----"
\$COUNTY\$	\$(COUNTY)	County name
\$TOWNS\$	\$(TOWN)	Town

BATCHPLOT

To plot cut sheets, a rectangular element drawn on level Border and in color 84, style 0, weight 0 has been placed at the outer edge of NHDOT border cells. BatchPlot looks for these elements when plotting cut sheets. When developing CAD/D drawings, elements of this color, style and weight should be avoided unless an element defining a batchplot limit is being created.

PART III – MX

FILE NAMING

MX files should be named in such a way that someone unfamiliar with the project can figure out what the file is for. MX projects are typically given names beginning with the town name followed by the state project number. For example: *Concord 12345.mmd*. Other file types are listed in the table below.

Type	Extension	Description
Input	.INP	Used to store line mode commands to create or modify MX strings
Output	.PRN	Used to store the results of an input file or interactive commands
Draw	.DRW	An input file that is used to create a display using a drawing macro or major option DRAW and/or ENHANCE commands
Journal	.JOU	A journal file stores commands issued during an MX session so they can be rerun at a later time

MODEL NAMING

Suggested MX model names are listed in *APPENDIX D – MX MODEL NAMING CONVENTION*, on page 49. Any variations from this convention shall be noted in the project journal file.

STRING LABELING

MX data is contained in strings and the strings are contained in models. Each string has a unique four-character label. Typically the first two characters of the string label are used to identify the type of string. NHDOT will continue to use the existing survey detail string labeling convention that was implemented with MOSS (the VMS version of MX). The existing detail string labeling convention is shown in *APPENDIX E – MX DETAIL STRING LABELING CONVENTION (TOPICAL)* on page 51 and *APPENDIX F – MX DETAIL STRING LABELING CONVENTION (ALPHABETICAL)* on page 57. Design string labels are listed in *APPENDIX G – MX DESIGN STRING LABELING CONVENTION* on page 63.

STYLE SETS

A style set is a collection of styles which is used to draw a complete model or a selected part of it in plan view. NHDOT style and features sets are stored on the network in MX's Public folder so they are accessible to all users. This eliminates the need to upgrade each workstation when changes are made.

FEATURE SETS

Feature sets are a means of grouping strings and identifying them with a description. They are used throughout MX to make it easier to select strings for subsequent operations. The strings belonging to a feature set are specified using a partial string name, and are drawn with a style set (usually having the same name as the feature set). For design detail, NHDOT uses a modified version of *mxroad.fns* to conform to MX design wizards. When transferring detail between MX and MicroStation, be aware that MicroStation elements are drawn based on the model's default style set. This may not be the same style set that was used to draw the MX DPW/DPF.

NHDOT Developed Style sets for MX drawings

Style Sets	Feature Sets	Description
ali8.pss	ali8.fns	Used to draw alignments. Alignments to be transferred to MicroStation are drawn with the <i>Create Alignment Drawing</i> add-in. See the CAD/D website for more details.
brd8.pss	brd8.fns	Used to transfer proposed bridge structure strings between MX and MicroStation.
catchment.pss	catchment.fns	Used to transfer drainage catchment models.
ctr8.pss	ctr8.fns	Used to draw and transfer contours.
env8.pss	env8.fns	Used to draw and transfer environmental features.
erw8.pss	erw8.fns	Used to draw and transfer existing Right-of-Way detail.
exd.pss	exd.fns	Used to draw existing and aerial survey detail in MX 2.6 that will become MicroStation v8 detail drawings. This style set is used to create the project's EXD and AIR dgn files.
ply8.pss	ply8.fns	Used to draw and transfer proposed roadway detail.
prw8.pss	prw8.fns	Used to transfer proposed Right-of-Way strings between MX and MicroStation.
pvm8.pss	pvm8.fns	Used to draw proposed pavement design.
trav.pss	trav.fns	Used to draw survey traverses.
xsu.pss	xsu.fns	To be set as the model default for cross section models. Cross sections to be transferred to MicroStation are drawn with the XS-MS macro.

DRAWING MACROS

In addition to the style and feature sets mentioned above, MX users can also draw detail and sections with drawing macros. A number of these macros have been developed and are available for download from the NHDOT website.

CROSS-SECTION SETTINGS FILES

Cross sections and profiles can be generated in a number of different ways. Using the cross-section wizard within MX allows the user to save parameters defining the cross-section set. These saved settings files have a .CSU extension and are stored in the project directory. The settings file will define the type of sections cut (based on the cross-section feature set used), models selected, and information about any special stations or skewed sections. By default, the cross-section wizard uses the information in the cross section model's default style set to determine the different types of cross-sections. String labels for cross sections are listed in *APPENDIX J – CROSS SECTION SET LABELS* on page 71.

MACRO SYMBOLS & LINES

Symbols for use with MX software, including standard line patterning symbols, are available in the MX .MMS and .MML file formats. Since line and symbol size is defined in the MX style sets, the same line and symbol definitions are used for both Imperial and metric projects. This data is available on the NHDOT website or can be requested through the Project Manager.

PART IV – OTHER PROJECT DATA

PROJECT JOURNAL FILES

PROJECT JOURNAL GUIDELINES

A Project Journal will be produced for each project. On consultant designed projects, a copy of the journal file will be delivered with each electronic project plan submission. The purpose for this journal is to aid downstream customers of the CAD/D data so they may utilize existing CAD/D work in their processes. The format of the journal will be an electronic file, either in text format or a format supported by Microsoft Word 2000. As a minimum, the journal will contain the following information:

- A listing (Index) of the project files, including brief descriptions of each file and where the file is located.
- Documentation about the CAD/D software used, special CAD/D decisions made, exceptions to standards that were made, problems encountered and work around, or other important issues that arose during the course of the CAD/D work. For example, if a custom line style needed to be created, the justification, resource file, and files where that line style was used would be documented in the Journal. Other documentation such as the design software used (including version number), particular software settings, and other information that would help a downstream user of the data understand where and how the data was created should be documented.

NHDOT has not established a specific format for the Journal file. The sample file shown on the following pages should be used a guideline for the type of information to be included and format that is expected.

Important data that should also be contained in the Journal include:

- All information necessary for the regeneration or use of those files by subsequent customers of the CAD/D data
- Document the design data, controlling alignment and profile names and geometry input/output files, relevant survey information, cross sections and the methodology used to obtain the final geometric controls in the CAD/D product.

The project journal must be kept up to date as the CAD/D design work progresses and be delivered with the project on the preferred media for archival purposes.

SAMPLE CAD/D PROJECT JOURNAL

CAD/D PROJECT JOURNAL

(12345_project_index.doc)
4/13/00

PROJECT JOURNAL

This file contains information about the project 12345 and the corresponding electronic files contained in the **project directory**. This file should be kept up to date and archived with the project's electronic files. When filling in the required information, please delete the instructions and examples in order to maintain a concise record.

PROJECT DESCRIPTION

State Project Number: 12345
Federal Aid Number: N/A
County: Merrimack
Project Manager: Project Manager
Project Designer: Project Designer
Project Directory: M:\pbt\town\12345\cadd\prj

SCOPE OF WORK

The scope of work for project 12345 goes here. Include as much detail as necessary to define the work done for the project.

PROJECT FILES

List any files that do not fit into the standard naming convention. Include a brief description of the data contained in each one.

MICROSTATION FILE INFORMATION

Non-Standard Drawings

List any drawings that are not on the standard naming convention list with a brief description of each one's contents.

Plot Information

List information about batch plot specifications, pen tables, or other features used to generate the plot files.

MX FILE INFORMATION (or information for other design programs used)

MX Topo input file: topo.inp

Preliminary Design Engineer: Your Name

Final Design Team Leader: Team Leader

<u>MX Design Input File Names</u>	<u>Description</u>
pdesign-mc0m.inp	The file that creates the alignment MCOM and design strings up to and including the interface stage.
psectmc0m.inp	Creates the old ground and proposed cross-sections for alignment MCOM

TEXT FILES

Include information about output files, genio files, or other ASCII files provided with the project drawings.

NON-STANDARD MODEL NAMES

Include information about any models that do not conform to standard naming conventions. These could be models developed as study alternatives or other special uses.

SPECIAL INFORMATION/COMMENTS

Include any information about special considerations or problems discovered during the design process.

MAIN LINE – "Main Street (NH 25)"

Survey (Plan Prep)

Master Alignment Model: SALIGN
 Master Alignment Name: .MC1S
 Triangle Model: Triangles
 Triangle String: TX00
 Cross Section Model: SSECTMC1S

Preliminary Design

Master Alignment Name: .MC1M

Master Alignment Model: PALIGN
 Design Model: PDESIGN MC1M
 Proposed Triangle Model:
 Proposed Triangle String:
 Cross Section Model:..... PDESIGN MC1M SECTIONS

Final Design

Master Alignment Name: .
 Master Alignment Model:
 Design Model:
 Proposed Triangle Model:
 Proposed Triangle String: .
 Cross Section Model:.....

SIDE ROAD – “Pleasant Street”

Survey (Plan Prep)

Master Alignment Model: SALIGN
 Master Alignment Name: .MC2S
 Triangle String: TX00
 Cross Section Model: SSECTMC2S

Preliminary Design

Master Alignment Name: .MC2A
 Master Alignment Model: PALIGN
 Design Model: PDESIGN MC2A
 Proposed Triangle Model:
 Proposed Triangle String: .
 Cross Section Model: PDESIGN MC2A SECTIONS

Final Design

Master Alignment Name: .
 Master Alignment Model:
 Design Model:
 Proposed Triangle Model:
 Proposed Triangle String: .
 Cross Section Model:.....

<u>Cross-Section Settings File (CSU)</u>	<u>Description</u>
mc1m.csu	Cross sections for Main St. including drives and skewed sections.
mc1m_all.csu	Cross-sections for Main St. cut at every point on the alignment for drainage study.
mc2a.csu	Cross sections for Pleasant St. including drives and skewed sections.

DRAWING QUALITY ASSURANCE / QUALITY CONTROL

To aid the consultant and in-house staff in developing a set of contract plans that conform to the requirements contained in this document, NHDOT has purchased QA/QC software that works with MicroStation drawings. These utilities, provided by GDM Software of Calgary, Alberta, will work from a set of "rule" files based on the established MicroStation standards. It is the intent of NHDOT to distribute a read-only version of this software, at no cost, to consultants with active NHDOT projects to be used to check the drawings before they are submitted. The software can also be used in the creation of the drawings. At this time, use of the drafting tools is optional although their use is strongly encouraged. There are no Bridge Design rule files.

The QA/QC software contains a number of components. They include:

QA_INPUT

QA_Input provides a "cascaded" or hierarchical flyout menu derived from the CAD/D drawing standards. Starting from the *Rules* pull-down menu, a feature is selected from the categories and sub-categories provided. QA_Input will set the correct level, weight, color, style, font, text size, active cell, etc. and activate the relevant placement command.

QUIKCHEK

QuikChek checks the active design file to ensure all elements have used valid drawing parameters. Errors are identified and corrected by category or by individual occurrence, at the user's option. Corrections are specified by selecting entries from the drawing standard, using the same interface described above in QA_Input. QuikChek will also suggest possible corrections from the closest matches to the drawing standards.

SPOT_FIX

Spot_Fix is a general-purpose proofreading tool. Spot_Fix will gray the display of an entire file, and then highlight items matching the rule(s) selected from the cascaded menu. The user can concentrate on one aspect of a file at a time, and spot anomalies with a quick visual examination. MicroStation commands or the tools provided in Spot_Fix can be used to correct the problem.

PART V - ENGINEERING CONSULTANT DELIVERABLE REQUIREMENTS

OVERVIEW

The purpose of this section is to establish the minimum acceptable criteria for electronic CAD/D deliverables. Obtaining drawings and ground models in a common format will reduce the amount of time spent becoming familiar with the designs if they are transferred from one designer to another and allows for their reuse in the future.

FILE FORMAT AND DELIVERY

REQUIREMENTS FOR SUBMITTING ELECTRONIC DATA TO NHDOT

All electronic data furnished to the NHDOT shall use the appropriate naming scheme and format for the type of data to be transmitted. It is very important to clearly communicate what is being transmitted and to describe the format of the transmitted files.

A letter is to be attached to **all submissions** stating briefly:

1. File content
2. File Format (zipped, MicroStation, MX, etc. and the utility used)
3. MX or MicroStation version
4. Number of CDs, DVDs, etc.
5. Files must be in the proper format before transmitting to NHDOT. **No translating of information by NHDOT personnel shall be required.**
6. If files are zipped or backed up, a brief explanation of the recommended procedure to extract the files should be included.
7. Versions of software must be current to or fully compatible with that of the NHDOT.
8. Each disk submitted shall be labeled and dated with a minimum of the State Project # and date. If a series of CDs are transmitted, the disk label shall also include the disk number and the total CDs of that set, (ex: 1 of 10). Other subsequent CDs shall be labeled so as to uniquely identify each group or set and shall include the sequence number followed by the total number in the group (ex: 2 of 10, 3 of 10, etc.)
9. NHDOT reserves the right to reject any file transmitted that does not conform to these requirements.

DATA SUBMISSION

In addition to hard copy drawings specified by the contract, the consultant shall submit electronic drawing files in MicroStation .DGN file format. Electronic files shall be delivered on one of the following in order of preference:

- a) CD-ROM
- b) Placed on DOT FTP site¹
- c) DVD

The final submission shall include all files necessary to reproduce the cut sheet drawings as well as copies of the original “roll-plan” drawings used to generate the cut sheets. Documentation of procedures and project history shall be maintained in a Project Journal File. An in-depth description of the Project Journal File is in *PART IV – OTHER PROJECT DATA* beginning on page 25. The Project Journal File will be provided with the submission. Any drawings not included in the NHDOT standard drawing list will be identified and will include a description of levels used on each drawing.

Detailed descriptions of the data to be provided by NHDOT to the consultant and expected deliverables at various stages of the project's development are included in the next section, NHDOT Design Process on page 34.

If MicroStation tables for linestyles, multilines, level tables, symbology tables, database, special fonts, or any special user defined feature is used, that information must be provided and shall become property of NHDOT. Similarly, any MX macro, symbol, linestyle, style set, or feature set developed by the consultant that is necessary to properly display the project data shall become property of NHDOT. Any MX input file developed to generate, enhance, or alter the project's design that the consultant feels would be beneficial to future designers of the project should also be provided. A name and description of each file must also be provided. NHDOT will not distribute these items to any other individual, consultant or State Transportation Department without prior permission of the developer.

DEVIATION FROM FORMAT

Any file to be submitted that deviates from the above-mentioned format must have prior NHDOT approval. The approval must be in writing with the name of the individual from NHDOT who permitted the varying format.

MICROSTATION ONLY DELIVERABLE

For projects that were initiated after April 18, 2002, NHDOT will only accept plan drawings that were developed in MicroStation's DGN format. Translations from AutoCAD or any other CAD/D software will no longer be allowed on those projects. Projects initiated before that date will continue to follow the requirements in place at the time the project was initiated. Engineering consultants may, at their discretion, choose to follow a later copy of these requirements.

¹ The NHDOT ftp site is located at <ftp://199.192.8/>. Contact your Consultant Reviewer for username and password information.

MICROSTATION PLOT FILES (FINAL DESIGN CONSULTANTS ONLY)

In addition to MicroStation format drawings, plot files of project cut sheets in PDF format will be required at the completion of the project. Plot files should be named with the convention for plan sheets outlined on page 7 using a .PDF file extension. The purpose of this requirement is to provide a viewable and reproducible copy of the drawing as it existed at the end of the consultant contract.

FILE CONVERSION

This information only applies to projects initiated prior to April 18, 2002.

Translation tables, conversion tables, or special software programs have not been created or standardized for exchanging information between common file formats such as DXF, DWG, ICES, IGES, or software such as AutoCAD, ARCVIEW, ARCINFO, GDS, etc.

MicroStation provides methods for exchanging select file types but data is often modified during the process. The Consultant is solely responsible for any translation and verification required to convert non-MicroStation graphics files to the current NHDOT MicroStation design file format. All translated design files shall conform to the standards adopted by NHDOT for electronic plans and the specifications required in this document. Those files shall be converted to MicroStation and thoroughly reviewed prior to transmitting to NHDOT.

The consultant shall be prepared to submit a sample cut sheet, profile, typical or detail, and/or cross-section sheet for review of conformity to the NHDOT CAD/D specifications at various stages of the project's development. As a minimum, the final design consultant should be prepared to submit electronic project drawings at the Preliminary Plans, Specifications & Estimate (PPS&E) and PS&E stages of the project. Depending on the project, NHDOT may request electronic submissions at a more or less frequent interval.

EXCHANGING RIGHT-OF-WAY DATA

Right-of-way data is routinely updated during the project's lifetime. This information is typically maintained by the NHDOT Bureau of Right-Of-Way for both in-house and Consultant-designed projects. Knowing that DOT staff and Consultants both need to work on the existing right-of-way (ERW) drawing, a process has been developed to ensure that this data is kept current and accurate.

It is the intention of the Consultant section of Highway Design to hold the master ERW drawing (abstracting) at the Department and send the consultant a copy when updates have been made. The Bureau of Right-Of-Way will continue to utilize Design History and that record will be maintained throughout the life of the project. This is in line with how business was conducted when the process included the ROW Abstracting mylar. The Bureau of Right-Of-Way will continue business as usual with the ability to make changes at any time during the design process with the understanding that the NHDOT Consultant Reviewer will be notified when changes have been made.

The process shall be:

- ERW drawing is created by the Bureau of Right-Of-Way and Design History is turned on.
- The Consultant receives a copy of the ERW drawing. They now have the ability to adjust text or make other cosmetic changes to improve appearance of the drawings when referenced to other design drawings.
- Updates are made by the NHDOT abstractor and a copy of the updated ERW drawing is sent to the Consultant.
- The Consultant overlays the Department's ERW with their ERW and incorporates any changes into their drawing. The Consultant either compares by color or reviews the Design History as intended.
- The Consultant deletes the ERW copy received from the Department.

NHDOT DESIGN PROCESS

This section is intended to describe the data that is to be provided when a project moves from one design phase to the next. There are two major transition points where Highway Design CAD/D data needs to be transferred: the turnover from the Plan Preparation Section to Preliminary Design and the one from Preliminary Design to Final Design.

PLAN PREPARATION

The Plan Preparation section is responsible for taking project survey and preparing the digital terrain model (DTM) and base drawings that will be used during the design process. They should also be the ones to initiate the Project Journal File described in *PART IV – OTHER PROJECT DATA* beginning on page 25.

By default, NHDOT design teams are working with 2-D drawings. If a consultant prefers to use 3-D drawings, this must be mentioned prior to obtaining survey or design data from the Department.

Electronic data to be provided by Plan Preparation to:

Preliminary Design and consultants using MX software:

1. Copy of the MX model file
2. Copy of the topo input file (TOPO.INP) containing survey data and Plan Preparation modifications/enhancements.
3. Copy of annotated MicroStation .DGN files developed for the project.
4. Copy of the Project Journal File

Consultants without MX software:

1. 3D DXF files of existing detail and triangulation generated from the MX model file
2. Copy of annotated MicroStation .DGN files developed for the project.
3. Copy of the Project Journal File

PRELIMINARY DESIGN

The Preliminary Design section is responsible for taking the data provided by the Plan Preparation section and designing the project up to the Public Hearing stage. This includes gathering all data necessary to prepare designs to be presented at the Public Officials Meeting, Public Informational Meetings, and Public Hearing.

Electronic deliverables expected from consultants at the completion of the Preliminary Design process:

Consultants using MX software:

1. Copy of the MX model file
2. Copy of any input files available to recreate the submitted design
3. Copies of any macro symbols and macro line definitions used on the project that are not included in the NHDOT standards
4. Copy of MicroStation .DGN files developed for the project
5. Copy of the Project Journal File

Consultants without MX software:

1. 3D DXF files of existing detail and triangulation generated from the design software
2. Copy of project horizontal and vertical alignments and associated design features in LandXML formats. Descriptions of file transfer formats can be found in *APPENDIX H – MX DATA TRANSFER FORMATS* beginning on page 65
3. Copy of MicroStation .DGN files developed for the project
4. Copy of the Project Journal File

Electronic data to be provided by NHDOT Preliminary Design section to:

Final Design and consultants using MX software:

1. Copy of the MX model file
2. Copy of the topo input file (TOPO.INP) containing survey data and Plan Preparation modifications/enhancements
3. Copy of MicroStation .DGN files developed for the project
4. Copy of the Project Journal File
5. Copy of the Project Public Hearing Plan in PDF format

Consultants without MX software:

1. Copy of project horizontal and vertical alignments and associated design features in LandXML formats. Descriptions of file transfer formats can be found in *APPENDIX H – MX DATA TRANSFER FORMATS* beginning on page 65
2. 3D DXF files of existing detail and triangulation generated from the MX model file
3. Copy of MicroStation .DGN files developed for the project
4. Copy of the Project Journal File
5. Copy of the Project Public Hearing Plan in PDF format

FINAL DESIGN

The Final Design section is responsible for taking the data provided by the Preliminary Design Section or Preliminary Design Consultant and designing the project up to the Contract Plans stage. This includes refining the project design as approved at the Public Hearing, preparing a project estimate, bid documents, and obtaining necessary construction permits.

Electronic deliverables expected from a Final Design consultant at the project's completion:

All Consultants

1. Copy of MicroStation .DGN files developed for the project
2. Copy of the Project Journal File
3. COGO and coordinate reports of each alignment similar in format to the ones shown in *APPENDIX I – CONSTRUCTION REPORTS* on page 69
4. Station and offset listing of proposed bounds
5. Plot files in PDF format of each contract plan sheet

Consultants using MX software:

1. Copy of the MX model file
2. Copy of any input files available to recreate the submitted design
3. Copies of any macro symbols and macro line definitions used on the project that are not included in the NHDOT standards

Consultants without MX software:

1. 3D DXF files of existing detail and triangulation generated from the design software
2. Copy of project horizontal and vertical alignments and associated design features in LandXML formats. Descriptions of file transfer formats can be found in *APPENDIX H – MX DATA TRANSFER FORMATS* beginning on page 65
3. If the project was designed with InRoads/SelectCAD, include files mentioned below

PROJECTS DESIGNED USING INROADS

If a project is designed with InRoads the following files should be delivered with other project data:

Surface Files (*.dtm): These files contain the existing and proposed ground information. In Version 7.x of InRoads they contain just the "triangulation". In the newest version of InRoads) these files

store the "triangulation" and other data. They will contain element types, i.e. edge of pavement, wetlands, buildings, and random shots.

Alignment Files (*.alg): These files contain the Horizontal, Vertical, and Superelevation information for a project.

Template Library (*.tml or *.itl): These files contain the templates, Material Tables, Cut/Fill Tables, and Decision Tables used to create the proposed design (in 8.5). Decision Tables work basically the same as an interface macro. Templates are similar to MX templates. In 8.7 Decision tables have been replaced with end conditions.

Roadway Library (*.rwl or *.ird): These files tell InRoads how to apply the templates and decision tables in 8.5 in 8.7 the Roadway Library is replaced with the Roadway designer. This file contains information similar to the Roadway library, it also allows designers to make changes in a file that can be rerun.

Preference Files (*.ini or *.xin): In InRoads these files control the display of design information; how InRoads draws profiles, sections, alignments, and design data.

Custom Cross Section files (*.xsc): These files contain a list of stations and offsets for InRoads to display sections. They will contain constant intervals, special stations, and skewed sections.

SPECIALIZED DEVELOPMENT BY DESIGN CONSULTANTS

Any specialized programs, macros, utilities, symbology, etc., developed by the consultant that are necessary to properly display drawings submitted to NHDOT shall be included with other project deliverables.

Submission of copies of other specialized programs, macros, utilities, symbology, etc. developed to improve MicroStation and MX drafting and design processes is encouraged. It is understood that NHDOT accepts these items without any guarantee of usefulness or expectations of support by the developer. In addition, NHDOT will not distribute these items to any other individual, consultant or State Transportation Department without prior permission of the developer.

NHDOT RESOURCES AVAILABLE FOR CONSULTANTS

To assist in the production of the required CAD/D files, NHDOT has provided MX and MicroStation support files available from the Department's web site. The website address is listed in the Disclaimer section at the beginning of this document.

PART VI - APPENDIX

APPENDIX A - MICROSTATION DRAWING NAMES

MicroStation drawing names will begin with the NHDOT state project number followed by the drawing type. The tables below show the text that will follow the project number along with a description of the drawing.

For example: 12345ALI.DGN would contain alignment data for project 12345.

PLAN DRAWINGS

(Names in *italics* have been added since the previous version of this document)

When attaching these drawings as reference files, it is recommended that the three character drawing name be used as the logical name.

Drawing Name	Content	Additional Details
AIR	Aerial Survey Data	All ground data obtained from aerial surveys.
ALI	Alignment	Existing and proposed roadway alignments & survey traverses
<i>BOR</i>	<i>Borings</i>	<i>Geotechnical boring locations</i>
<i>BRD</i>	<i>Bridge Information</i>	<i>Proposed bridge layout</i>
CLR	Color Plan	Color fill patterns typically used for project meetings and presentations. This is not the same as the HER drawing developed for the Public Hearing which has a clearly defined format and color legend.
CTR	Existing Contours	
DET	Detour	
EDU	Existing Digitized Utilities	Information received from utility companies that was added to the drawing by DOT or Consultant staff.
ENV	Environment	Wetland or flood zone delineations, identifications of historic properties, and other environmental concerns
ERW	Existing Right-of-Way	
EXD	Existing Detail	Data obtained by ground survey.
EXF	Field Check Data	Ground data pick up during field checks
HER	Hearing Plan	
HHO	Informational Handout	The Informational Handout is prepared for the Public Hearing.
LLC	Large Location Map	LLC is typically used at meetings on larger projects. It shows the project location in relation to the surrounding area.
LND	Landscaping	
LOC	Project Location Map	The LOC drawing shows the project's location in relation to the surrounding area. It is one of the drawings used in development of the Front Sheet.
MTH	Match Lines	Part of the cut sheet process. This drawing contains outlines representing the areas to be displayed on each sheet.

Drawing Name	Content	Additional Details
PCN	Proposed Contours	
PDR	Proposed Drainage	
PGR	Proposed Guardrail	
PLY	Proposed Layout	
PNT	Proposed Notes	
PRO_MC## Profile		Profile drawings will be named with "PRO_" followed by the four character alignment label for projects designed in MX. Projects not using MX will need some other method of identification.
PRW	Proposed Right-of-Way	
PSG	Proposed Signalization	
PSN	Proposed Signing	
PUT	Proposed Utilities	
PVM	Pavement Markings	
PWT	Proposed Wetlands	
PXB	<i>Pictures – Bridge Design</i>	The PX series of drawings are used for storing raster photographs. There are separate drawings for each design bureau to indicate who added the images..
PXBM	<i>Pictures – Bridge Maintenance</i>	
PXE	<i>Pictures – Environmental</i>	
PXH	<i>Pictures – Highway Design</i>	
PXM	<i>Pictures – Materials & Research</i>	
PXR	<i>Pictures – Right-of-Way</i>	
PXT	<i>Pictures – Traffic</i>	
SSD	<i>Superceded Details</i>	The SSD drawing can store details that have been changed and are no longer valid, but want to be kept in case they are needed in the future.
TXT	Existing Text	
XS_MC## Cross-section		Cross-section drawings will be named with "XS_" followed by the four character alignment label for projects designed in MX. Projects not using MX will need some other method of identification.
XSU	Section Details	

CUT SHEET DRAWING TYPES

or ## indicates a sequential number

B##	Base Sheets	FSW	Front Sheet-Wetlands	S##	Signing
C##	Curbing & Pavement Layout	G##	General Plans	SG#	Signalization
D##	Drainage	L##	Landscaping	SM#	Summary Sheet
E##	Detour	M##	Pavement Marking	ST#	Sign Te#t Layout
FSC	Front Sheet- Construction	P##	Profiles	T##	Traffic Control Plans
FSR	Front Sheets-ROW	PL#	Property Layout	TY#	Typicals
		R##	Right-of-Way	W##	Wetland
		RS#	Row Summary Sheet		

BRIDGE DESIGN DETAIL DRAWINGS

For projects that contain multiple bridges the six digit bridge inventory number shall be used after the names below. For example: 12345A-Abut123456.DGN will contain the abutment A masonry for the 12345 on the bridge 123/456.





AbutA			
A-Abut	Abutment A Masonry		
A-Rebar	Abutment A Reinforcement		
A-Wings	Abutment A Wings		
A-ReWings	Abutment A Wings Reinforcement		
A-Foot	Footing A Masonry		
A-ReFoot	Footing A Reinforcement		
AbutB			
B-Abut	Abutment B Masonry		
B-Rebar	Abutment B Reinforcement		
B-Wings	Abutment B Wings		
B-ReWings	Abutment B Wings Reinforcement		
B-Foot	Footing B Masonry		
B-ReFoot	Footing B Reinforcement		
Pier			
Pier1	Pier 1 Masonry		
Re-Pier1	Pier 1 Reinforcement		
Pier2	Pier 2 Masonry		
Re-Pier2	Pier 2 Reinforcement		
Box			
BX-Deck	Box Deck	BX-ReWings	Box Wings Reinforcement
BX-ReDeck	Box Deck Reinforcement	BX-Walls	Box Walls
BX-Foot	Box Footing	BX-ReWalls	Box Walls Reinforcement
BX-ReFoot	Box Footing Reinforcement	BX-Detls	Box Details
BX-Wings	Box Wings Masonry		
Frame			
FR-Detls	Frame Details	FR-ReBLeg	Frame Leg B Reinforcement
FR-Foot	Frame Footing	FR-Deck	Frame Deck
FR-ReFoot	Frame Footing Reinforcement	FR-ReDeck	Frame Deck Reinforcement
FR-ALeg	Frame Leg A	FR-Wings	Frame Wings
FR-ReALeg	Frame Leg A Reinforcement	FR-ReWings	Frame Wings Reinforcement
FR-BLeg	Frame Leg B		
PrelimPlans			
Pre-Gen	Preliminary Genplan		
Pre-Site	Preliminary Site Plan		
BrSite			
Genplan	Genplan	Devl-View	Developed Views
Siteplan	Siteplan	BrNotes	Bridge Notes
Borings	Boring Logs	BrDetour	Bridge Detour
Bor-Req	Boring Request		
Super			
DeckDetls	Deck Details	Shoes	Bridge Shoes
DeckBars	Deck Reinforcing		
DeckSect	Deck Section		
Girder	Girder Layout and Details		
FramePlan	Framing Plan		
SSDetls	Super Structure Details		


APPENDIX B - LEVEL MAPPING CONVENTION

Note: MicroStation level information was included in previous editions of this document. To reduce the potential for errors and conflicting data, this information has been removed. The latest mapping convention can be found on the NHDOT web-site at the address listed in the Disclaimer section of this document. Previous versions of the level mapping will be maintained on the website.

APPENDIX C - NHDOT CUSTOM LINSTYLES & FONT

	0		F		F	Fire-Exist
	1		PF		PF	Fire-Prop
	2		G		G	Gas-Exist
	3		PG		PG	Gas-Prop
	4					Ground-Exist
	5					GroundBr
	6					HOTL
	7					Hearing
	ArBegOpn					Hearing-m
	ArBegSid					Hedge
	ArEndOpn					Leader
	ArEndSid					Leader2
	Arrow					LeaderBr
	Arrow2					Ledge
	Arrow3					LedgeBr
	ArrowBr					Light-Exist
	BmGrDbI					Light-Prop
	BmGrLt					MagDetSleeve
	BmGrRt					NtnlForest
	Border					DHW
	Break					PCurbLt
	BreakBr					PCurbRt
	BreakDimBr					PaveMark
	Bush					PedRail
	CbIGrLt					PipeE1050
	CbIGrRt					PipeE12
	ConduitL					PipeE1200
	ConduitL-Prop					PipeE1350
	Conduits					PipeE15
	Conduits-Prop					PipeE1500
	County					PipeE1650
	CurbLt					PipeE18
	CurbRt					PipeE1800
	CutLt					PipeE2100
	CutRt					PipeE24
	Dim2					PipeE2400
	DimBr					PipeE30
	Ditch					PipeE36
	DrainPipe					PipeE375
	DrainPipe-Prop					PipeE42
	Electric-Exist					PipeE450
	Electric-OH					PipeE48
	Electric-Prop					
	FP100					
	FP500					
	FW					
	Fence-Barbed					
	Fence-Barbed(short)					
	Fence-Nobarb					
	Fence-Nobarb(short)					
	Fill					

	PipeE54		PipeP72
	PipeE60		PipeP750
	PipeE600		PipeP84
	PipeE66		PipeP900
	PipeE72		PipeP96
	PipeE750		PropLine
	PipeE84		QML
	PipeE900		ROW
	PipeE96		RRRow
	PipeP1050		Railroad
	PipeP12		RetWallLt
	PipeP1200		RetWallRt
	PipeP1350		RockLine
	PipeP15		RockLineBr
	PipeP1500		S Sewer-Exist
	PipeP1650		PS Sewer-Prop
	PipeP18		SheetPile
	PipeP1800		StateLine
	PipeP2100		ST Steam-Exist
	PipeP24		PST Steam-Prop
	PipeP2400		StoneFill
	PipeP30		StoneWall-Exist
	PipeP300		StoneWall-Prop
	PipeP36		StoneWall-Short
	PipeP375		StreamLt
	PipeP42		StreamRt
	PipeP450		T B Z TBZ
	PipeP48		T O B TOB
	PipeP54		T O B O H W TOBOHW
	PipeP60		T Tele-Exist
	PipeP600		PT Tele-Prop
	PipeP66		Tick
			TownLine
			TrafBarls
			UnderDrain
			UnderDrain-Prop
			W Water-Exist
			PW Water-Prop
			D W Wetland
			WoodsLt
			WoodsRt
			XPipeE1050



nh_engineering (Font 180) Special Characters

033 = !	128 = >	161 = $\frac{3}{64}$	194 = Φ	227 =
034 = "	129 = $\frac{1}{2}$	162 = $\frac{5}{64}$	195 = M	228 =
035 = #	130 = $\frac{1}{4}$	163 = $\frac{7}{64}$	196 = OM	229 = U
036 = \$	131 = $\frac{3}{4}$	164 = $\frac{9}{64}$	197 = B	230 = U
037 = %	132 = $\frac{1}{8}$	165 = $\frac{11}{64}$	198 = G	231 = U
038 = &	133 = $\frac{3}{8}$	166 = $\frac{13}{64}$	199 = Δ	232 = U
039 = '	134 = $\frac{5}{8}$	167 = $\frac{15}{64}$	200 = \pm	233 = U
040 = (135 = $\frac{7}{8}$	168 = $\frac{17}{64}$	201 = J	234 = U
041 =)	136 = $\frac{1}{16}$	169 = $\frac{19}{64}$	202 = C	235 = U
042 = *	137 = $\frac{3}{16}$	170 = $\frac{21}{64}$	203 = J	236 = U
043 = +	138 = $\frac{5}{16}$	171 = $\frac{23}{64}$	204 = C	237 = \square
044 = ,	139 = $\frac{7}{16}$	172 = $\frac{25}{64}$	205 = J	238 = \circ
045 = -	140 = $\frac{9}{16}$	173 = $\frac{27}{64}$	206 = J	239 = \square
046 = .	141 = $\frac{11}{16}$	174 = $\frac{29}{64}$	207 = L	240 = \square
047 = /	142 = $\frac{13}{16}$	175 = $\frac{31}{64}$	208 = J	241 = \rightarrow
058 = :	143 = $\frac{15}{16}$	176 = $\frac{33}{64}$	209 = L	242 = \rightarrow
059 = ;	144 = $\frac{1}{32}$	177 = $\frac{35}{64}$	210 = J	243 = \rightarrow
060 =	145 = $\frac{3}{32}$	178 = $\frac{37}{64}$	211 = L	244 = J
061 = =	146 = $\frac{5}{32}$	179 = $\frac{39}{64}$	212 = L	245 = *
062 = C	147 = $\frac{7}{32}$	180 = $\frac{41}{64}$	213 = J	246 = Q_{10}
063 = ?	148 = $\frac{9}{32}$	181 = $\frac{43}{64}$	214 = L	247 = Q_{25}
064 = @	149 = $\frac{11}{32}$	182 = $\frac{45}{64}$	215 = L	248 = Q_{50}
091 = [150 = $\frac{13}{32}$	183 = $\frac{47}{64}$	216 = C	249 = Q_{100}
092 = \leq	151 = $\frac{15}{32}$	184 = $\frac{49}{64}$	217 = C	250 = C
093 =]	152 = $\frac{17}{32}$	185 = $\frac{51}{64}$	218 = C	251 = f_{c}
094 = °	153 = $\frac{19}{32}$	186 = $\frac{53}{64}$	219 = C	252 = $^{\circ}$
095 = _	154 = $\frac{21}{32}$	187 = $\frac{55}{64}$	220 = C	253 = $^{\circ}$
096 = \angle	155 = $\frac{23}{32}$	188 = $\frac{57}{64}$	221 = C	254 = U
123 = {	156 = $\frac{25}{32}$	189 = $\frac{59}{64}$	222 = C	255 = $^{\circ}$
124 = \geq	157 = $\frac{27}{32}$	190 = $\frac{61}{64}$	223 = C	
125 = }	158 = $\frac{29}{32}$	191 = $\frac{63}{64}$	224 = C	
126 = '	159 = $\frac{31}{32}$	192 = C	225 = C	
127 = <	160 = $\frac{1}{64}$	193 = R	226 = C	

Character 245 is used in dimensions where a character appearing as an * is needed. The normal * will show the dimension value.

APPENDIX D – MX MODEL NAMING CONVENTION

Note: These are the most commonly encountered models on a project. When creating additional models, use names that easily and accurately reflect the information contained in the model.

PLAN PREPARATION MODELS

(Models appear in approx. order of creation)

RAxxxxx Model containing a field surveyed traverse string PSSA. Traverses may be received as separate dump files (eg. RAxxxxx.SDR, RBxxxxx.SDR, etc. - where xxxxx is the project number). Individual traverses are typically combined to create a single traverse in this model. The Survey Section is responsible for closing/adjusting traverses.

TOPO Model containing existing project detail/topo strings as recorded in the field by survey data collectors. This model is created by editing then merging individual topo dump files (eg. TAxxxxx.SDR, TBxxxxx.SDR, etc. - xxxxx is the project number).

AERIAL DETAIL Model containing existing aerial survey detail obtained from an outside agency.

BOUNDARY A model containing one or more boundary strings (BDRY, BY01, etc.) Boundary strings may be used in merging models or controlling creation and trimming of the triangle string (although PBRK strings have generally superseded boundary string needs in triangulation).

TRIANGLES Model containing the triangulation string (TRIA) created by using select topo detail string information. Triangulation interrelates points on and between strings, creating a surface from which elevations can be extracted at any location.

CONTOURS Model containing the existing ground contour strings (0 [zero] = major, D = minor) created by surfacing (contouring) the TRIANGLES model.

SALIGN Model containing reference master alignments (MCxS) created using center of road shots (CO) to establish tangents and adding approximate curves (to nearest 15'). Reference alignments are used to cut profiles and cross sections which assist in verifying the accuracy of the TOPO & CONTOURS models via a field check. Existing ground elevations are attached to the master strings by sectioning them over the TRIANGLES model. Strings in this model must be refined (drive points added, etc.) if they are to be used for design purposes.

SSECT MCxS Model containing existing ground cross sections cut referencing the master string MCxS in SALIGN. Existing ground sections are cut over the TRIANGLES model at each point along the master string and assigned string labels beginning with 'E'. Separate section models are maintained for each unique master string.

NOTE: THESE MODELS ARE RECORD FILES! NO MODIFICATIONS ARE TO BE MADE WITHOUT THE PRIOR APPROVAL OF PLAN PREP.

PRELIMINARY DESIGN MODELS

PALIGN Model for storing all master (MC) and geometry (GC) strings with proposed elevations, as well as the corresponding Existing Ground 'OC' strings. During early stages of a project, a large number of alignments may be created. Side road alignments are sometimes stored in a model named after the road.

Note: Master 'MC' and the associated existing ground 'OC' strings must reside in the same model to be drawn up or plotted together on a profile.

PDESIGNMCxx This model contains the master string 'MCxx' with proposed elevations (copied from PALIGN), and the associated template (created with DESIGN options) and Earthworks (INTERFACe options) strings. Separate design models are maintained for each master string.

PDRIVES Model for storing all driveway alignments.

PSECTMCxx Model containing all cross sections for master string MCxx. Section Sets are listed in Cross Section Set Labels. Separate cross section models are maintained for each master string.

For the most accurate results, existing cross sections 'E' should be cut over the TRIANGLES model.

SIGHT LINES MCxx Model intended to store sight lines and visibility envelope strings resulting from Visibility Analysis. Separate sight line models are maintained for each master string.

NOTE: THESE MODELS ARE INTENDED FOR PRELIMINARY USE ONLY AND ARE TECHNICALLY CONSIDERED 'RECORD' FILES. NO MODIFICATIONS ARE TO BE MADE WITHOUT THE APPROVAL OF THE PRELIMINARY DESIGN ENGINEER.

FINAL DESIGN MODELS

When a project is turned over, the preliminary design engineer shall provide the team with a list of the models and pertinent strings in each. The final team will copy the pertinent strings into the appropriate Final Design models. Final work should not be done on Preliminary Design models.

If the number of models becomes excessive, the Team should consider utilizing the MX ARCHIVE option. This enables removal of infrequently used models from the active MODEL.FIL and placement into an ARCHOLD.FIL. Use the LIST or RETRIEVE options to view or retrieve model information.

OG FALIGN	Model descriptions are identical to Preliminary Design models with the exception that they are for Final Design use.
FALIGN	
FDESIGN MCxx	
FSECT MCxx	

FTRIANGLES Model containing the final triangulation string (TRIP) based on the proposed design template and interface strings contained in the FDESIGN MCxx model. A PBRK or boundary string may be created to prevent contours from being generated outside the limits of the interface (slope) lines. These string(s) would be stored in the appropriate FDESIGN MCxx model.

FCONTOURS Model to contain the final contours generated by surfacing the FTRIANGLES model.

NOTE: THESE ARE THE MOST COMMONLY ENCOUNTERED MODELS ON A PROJECT. WHEN CREATING ADDITIONAL MODELS, USE NAMES THAT EASILY AND ACCURATELY REFLECT THE INFORMATION CONTAINED IN THE MODEL.

APPENDIX E – MX DETAIL STRING LABELING CONVENTION (TOPICAL)

Items added since the previous edition are shown in *italic* print. This list was current at the time of publication. For the most up-to-date listings, visit the CAD/D website - <http://webster.state.nh.us/dot/its/cadd/mx/mosslabl.htm>.

GENERAL USE:

Bench mark.....	PBMK
Boring.....	PBOR
PBRK Strings	PBRK
Boundary String	BY
Drill hole.....	PDHL
Level string.....	L
Spot elevations.....	PELV
Spot elevations - Not at Ground	PEVV
Survey traverse string.....	PSSA

Point labels within survey traverse string (PSSA)	
Traverse	S
Survey fly station	P

BOUNDARIES:

County line	BC
Iron pin or pipe	PIPN
National forest line	BN
Bound	PBND
Project marker	PRJM
Proposed construction easement.....	CE
Proposed drainage easement.....	DE
Property line	BP
Bound other	PCON
Right-of-way, controlled access	BRC
Right-of-way, limited access	BRL
Right-of-way line.....	BRW
Right-of-way, railroad	BRR
State line	BSL
State line marker.....	PSLM
Town line.....	BT
Town line marker.....	PTLM

ROADWAY FEATURES:

Center of road.....	CO
Edge of traveled way	TW
Edge of pavement.....	EP
Lane markings	LM
Driveway	DR
Trail	TL
Curb - Left.....	CL
Curb - Right.....	CR
Curb - Top	TC
Beam guard rail - Left	BL
Beam guard rail - Right.....	BR
Cable guard rail - Left	GL

Cable guard rail - Right	GR
Double face beam guard rail.....	DF
Jersey barrier	JB
Ditch line	DL
Bottom of slope	BS
Top of slope.....	TS

BRIDGE FEATURES:

Bridge deck.....	BG
Bridge abutment - Top.....	TB
Bridge abutment - Bottom	BB
Expansion joint.....	EJ
Exposed bridge footing - Top.....	TF
Exposed bridge footing - Bottom	BF
Top of bridge pier.....	TP
Wing wall - Top.....	WT
Wing wall - Bottom	WB
Rip-rap.....	RP
Bridge spot elevations	PEBV
Bridge miscellaneous detail features - point string.....	PMBF

RAILROAD FEATURES:

Railroad	RR
Railroad sign.....	PRSN
Railroad signal.....	PRSL
Railroad switchstand.....	PRSW

STRUCTURES:

Building sill	BD
Concrete Pad (gas station island; etc.).....	CP
Ground at/near building.....	BE
Foundation/Ruin	FD
Sill Point	PSIL
Steps	SP
Sidewalk	SK
Fence - Barbed wire.....	FB
Fence - Other	FO
Retaining wall - Left ---^---^---	RL
Retaining wall - Right ---v---v---	RW
Retaining wall - Top.....	TR

UTILITIES:

Catch basin top	PCBD
Catch basin/Drop inlet sump	PSUM
Dam	DM
Dam - bottom.....	DB
Drainage pipe (Survey: use IGL for dir. shots).....	DP
Drop inlet top.....	PDID
Fire hydrant	PHYD
Fuel Tank.....	PFTK
Gas Pump.....	PGAS
Gas pumps	GP
Gas shutoff.....	PGSO

Guy pole or stub	PGUY
Guy wire anchors.....	PANC
Headwall, culvert end - Bottom.....	BH
Headwall - Top.....	TH
Joint power and telephone pole	PJNT
Light on joint pole	PLTJ
Light on power pole.....	PLTP
Light pole.....	PLIT
Manhole - Drainage.....	PMHD
Manhole - Electric	PMHE
Manhole - Gas	PMHG
Manhole - Sewer.....	PMHS
Manhole - Telephone.....	PMHT
Manhole - Water.....	PMHW
Pole.....	PPOL
Power pole.....	PPWR
Sluiceway	SU
Storage tanks	SG
Storage tank fill cap.....	PSTT
Public telephone	PBTH
Telephone/telegraph pole.....	PTEL
Transmission line/Aerial electric lines	AE
Transmission line tower.....	PPTR
Utility junction box.....	PJCT
Underdrain.....	UD
Underground Electric	UE
Underground Gas.....	UG
Underground Sewer.....	US
Underground Telephone	UT
Underground Water	UW
Water gate.....	PWGT
Water shutoff.....	PWSO

SIGNING/SIGNALS:

Controller cabinet	PCCT
Handhole.....	PHHL
Loop detector.....	SD
Magnetic detector sleeve	DS
Mast arm pole	PMAP
Pullbox.....	PPBX
Sign - Single post.....	PSGN
Sign - Double post.....	PSND
Sign - Billboard or other large sign (string feature)	SN
Signal conduit.....	SC
Street light conduit.....	LC
Traffic signal without mast arm.....	PSGL

OTHER GROUND FEATURES:

Athletic Field	AF
Berm	BM
Boulder	PBDR
Bush.....	PBUS
Cemetery.....	CM
Gate	GA
Gate post	PGPT

Ground light/yard light	PGLT
Fire tower.....	PFTR
Flag pole	PFPL
Gravestone.....	PGRV
Hedge.....	HE
High water mark	HW
Intermittent or small stream.....	ST
Lamp post/private light pole.....	PLPT
Leachfield	LF
Mail box.....	PMBX
Miscellaneous detail features - Point string.....	PMDF
<i>Miscellaneous detail features - Not at Ground</i>	<i>PMVF</i>
Miscellaneous detail features - Feature string	FM
Monuments/statues or other related items	PMON
Ornamental features (flower beds; etc.)	OR
Parking Meter	PARK
Pool.....	QP
Post - all types	PPST
Ramp - Boat; etc.	RM
Ridge line.....	RD
Rock outcrop	RO
Satellite dish	PDAT
Septic Tank.....	PSTK
Shore line - Left.....	SL
Shore line - Right.....	SR
Stockpile/lumber pile.....	QS
Stockpile2	SO
Stone wall	SW
Stump.....	PSTP
Swamp/marsh or wet area.....	WA
Swamp symbol	PSWP
Test pit	PTPT
Tree - Coniferous.....	PTCS
Tree - Deciduous	PTDS
Vent pipe - Outlet	PVNT
Waterfall.....	WF
Well	PWEL
Wetland	WD
Woods line or brush line - Left.....	WL
Woods line or brush line - Right.....	WR

CONTOURS:

Index contour - Approximate.....	CA
Index contour - Approx. depression	CB
Index contour - Depression.....	CD
Index contour - Standard	CS
Intermediate contour - Approximate.....	ZA
Intermediate contour - Approx. depression	ZB
Intermediate contour - Depression.....	ZD
Intermediate contour - Standard	ZF

AERIALS:

Text - Dense Trees.....	*DT
Text - Grid Text.....	*GR
Asphalt Pad.....	AP

<i>Buildings</i>	BA
<i>Curb Bottom</i>	CB
Culvert - Aerial Mapping	CU
Deck.....	DK
Driveway Unpaved.....	DU
Edge of Gravel Road	EG
Stream or river flow arrow	FA
Grid.....	GD
Gravel Shoulder.....	GS
Obscured Tank.....	KO
Back of Curb.....	NC
Back of Curb Obscured	ND
Back of Curb - No Elevation Change from Bottom.....	NE
Obscured Railroad	NO
Obscured area	OA
Obscured Bridge.....	OB
Obscured Curb - Bottom Right.....	OC
Obscured Drive.....	OD
Obscured Shoulder	OE
Obscured Fence	OF
Obscured Guardrail.....	OH
Obscured Structure	OI
Obscured Wall.....	OJ
Obscured Deck	OK
Obscured Lane Marking.....	OL
Obscured Misc. Object.....	OM
Obscured Sign	ON
Obscured Concrete Pad	OO
Obscured Pavement	OP
Obscured Pool	OQ
Obscured Sidewalk.....	OS
Obscured Headwall.....	OT
Obscured Culvert.....	OU
Obscured Wetland	OW
Obscured Water.....	OX
<i>Obscured Ramp/Dock</i>	OY
Obscured Catch Basin	PCBO
Obscured Drain.....	PDIO
Spot Elevation	PDTM
Obscured Flagpole.....	PFPO
Fence Post.....	PFPS
Obscured Hydrant.....	PHYO
Obscured Lightpole	PLPO
Obscured Manhole.....	PMHO
Obscured Pole.....	POPL
Obscured Post.....	POPS
Horizontal Vertical Control.....	PPHV
Obscured Sign	PSGO
Obscured Traffic Signal.....	PSOL
Tree from Aerial Mapping.....	PTR1
Obscured Steps	SQ
<i>Curb Top</i>	TC
Obscured Top of Curb	TD
Top of Curb - No Elevation Change from Bottom	TE
Tank.....	TK
Transmission Tower	TN

Obscured Trail	TO
<i>Retaining Walls</i>	<i>TR</i>
Obscured Utility	UO
Break lines	X

PIT SURVEYS:

(Survey use only)

Bottom of slope	BS
Level string	L
Limit of pit	LP
Limit of work	LW
Old ground	OG
Stockpile	SO
Top of slope	TS
Waste	WS

TEXT STRINGS:

(Not for survey use)

Building name	*BD
Cemetery name	*CM
County name	*CT
Dam name	*DM
General name	*GN
Miscellaneous name	*MS
Ocean name	*OC
Pipeline name	*PI
Pole numbers	*PL
Pool text	*PO
Road names	*RD
Railroad name	*RR
River name	*RV
Spot elevations	*E
State name	*ST
Town name	*TW

APPENDIX F – MX DETAIL STRING LABELING CONVENTION (ALPHABETICAL)

Items added since the previous edition are shown in italic print. This list was current at the time of publication. For the most up-to-date listings, visit the CAD/D website - <http://webster.state.nh.us/dot/its/cadd/mx/mossalph.htm>.

*BD	Building name
*CM	Cemetery name
*CT	County name
*DM	Dam name
*DT	Aerial Text - Dense Trees
*E	Spot elevations
*GN	General name
*GR	Aerial Text - Grid
*MS	Miscellaneous name
*OC	Ocean name
*PI	Pipeline name
*PL	Pole numbers
*PO	Pool text
*RD	Road names
*RR	Railroad name
*RV	River name
*ST	State name
*TW	Town name
AE	Transmission line/Aerial electric lines
AF	Athletic Field
AP	Asphalt Pad - Aerial Surveys
<i>BA</i>	<i>Building - Aerial Surveys</i>
BB	Bridge abutment - Bottom
BC	County line
BD	Building sill
BE	Ground at/near building
BF	Exposed bridge footing - Bottom
BG	Bridge deck
BH	Headwall, culvert end - Bottom
BL	Beam guard rail - Left
BM	Berm
BN	National forest line
BP	Property line
BR	Beam guard rail - Right
BRC	Right-of-way, controlled access
BRL	Right-of-way, limited access
BRW	Right-of-way line
BS	Bottom of slope
BS	Bottom of slope - Pit surveys
BSL	State line
BT	Town line
BY	Boundary String
CA	Index contour - Approximate
<i>CB</i>	<i>Curb Bottom - Aerial Surveys</i>
CB	Index contour - Approx. depression
CD	Index contour - Depression
CE	Proposed construction easement
CL	Curb - Left

CM	Cemetery
CO	Center of road
CP	Concrete Pad (gas station island; etc.)
CR	Curb - Right
CS	Index contour - Standard
CU	Culvert - Aerial Mapping
DB	Dam - bottom
DE	Proposed drainage easement
DF	Double face beam guard rail
DK	Deck - Aerial Surveys
DL	Ditch line
DM	Dam
DP	Drainage pipe (Survey: use IGL for dir. shots)
DR	Driveway
DS	Magnetic detector sleeve
DU	Driveway Unpaved - Aerial Surveys
EG	Edge of Gravel Road - Aerial Surveys
EJ	Expansion joint
EP	Edge of pavement
FA	Stream or river flow arrow - Aerial Surveys
FB	Fence - Barbed wire
FD	Foundation/Ruin
FM	Miscellaneous detail features - Feature string
FO	Fence - Other
GA	Gate
GD	Grid - Aerial Surveys
GL	Cable guard rail - Left
GP	Gas pumps
GR	Cable guard rail - Right
GS	Gravel Shoulder - Aerial Surveys
HE	Hedge
HW	High water mark
JB	Jersey barrier
KO	Obscured Tank - Aerial Surveys
L	Level string
L	Level string - Pit surveys
LC	Street light conduit
LF	Leachfield
LM	Lane markings
LP	Limit of pit - Pit surveys
LW	Limit of work - Pit surveys
NC	Back of Curb - Aerial Surveys
ND	Obscured Back of Curb - Aerial Surveys
NE	Back of Curb - No Elevation Change from Bottom - Aerial Surveys
NO	Obscured Railroad - Aerial Surveys
OA	Obscured area - Aerial Surveys
OB	Obscured area of bridge - Aerial Surveys
OC	Obscured Curb - Bottom Right - Aerial Surveys
OD	Obscured Drive - Aerial Surveys
OE	Obscured Shoulder - Aerial Surveys
OF	Obscured Fence - Aerial Surveys
OG	Old ground - Pit surveys
OH	Obscured Guardrail - Aerial Surveys
OI	Obscured Structure - Aerial Surveys
OJ	Obscured Wall - Aerial Surveys
OK	Obscured Deck - Aerial Surveys

OL	Obscured Lane Marking - Aerial Surveys
OM	Obscured Misc. Object - Aerial Surveys
ON.....	Obscured Sign - Aerial Surveys
OO.....	Obscured Concrete Pad - Aerial Surveys
OP	Obscured Pavement - Aerial Surveys
OQ.....	Obscured Pool - Aerial Surveys
OR	Ornamental features (flower beds; etc.)
OS	Obscured Sidewalk - Aerial Surveys
OT	Obscured Headwall - Aerial Surveys
OU.....	Obscured Culvert - Aerial Surveys
OW	Obscured Wetland - Aerial Surveys
OX.....	Obscured Water - Aerial Surveys
OY	<i>Obscured Ramp/Dock - Aerial Surveys</i>
PANC	Guy wire anchors
PARK	Parking Meter
PBDR	Boulder
PBMK.....	Bench mark
PBND	Bound
PBOR	Boring
PBRK.....	<i>PBRK Strings</i>
PBTH	Public telephone
PBUS.....	Bush
PCBD	Catch basin top
PCBO	Obscured Catch Basin - Aerial Surveys
PCCT.....	Controller cabinet
PCON	Bound other
PDAT	Satellite dish
PDHL	Drill hole
PDID	Drop inlet top
PDIO	Obscured Drain - Aerial Surveys
PDTM.....	Spot Elevation - Aerial Surveys
PEBV	Bridge spot elevations
PELV.....	Spot Elevations
PEVV	Spot Elevations - Not at Ground
PFPL	Flag pole
PFPO	Obscured Flagpole - Aerial Surveys
PFPS	Fence Post - Aerial Surveys
PFTK.....	Fuel Tank
PFTR.....	Fire tower
PGAS	Gas pump
PGLT.....	Ground light/yard light
PGPT	Gate post
PGRV	Gravestone
PGSO	Gas shutoff
PGUY	Guy pole or stub
PHHL	Handhole
PHYD	Fire hydrant
PHYO	Obscured Hydrant - Aerial Surveys
PIPN.....	Iron pin or pipe
PJCT	Utility junction box
PJNT	Joint power and telephone pole
PLIT	Light pole
PLPT	Lamp post/private light pole
PLPO	Obscured Lightpole - Aerial Surveys
PLTJ.....	Light on joint pole
PLTP	Light on power pole

PMAP	Mast arm pole
PMBF	Bridge miscellaneous detail features - point string
PMBX	Mail box
PMDF	Miscellaneous detail features - Point string
PMHD	Manhole - Drainage
PMHE	Manhole - Electric
PMHG	Manhole - Gas
PMHO	Obscured Manhole - Aerial Surveys
PMHS	Manhole - Sewer
PMHT	Manhole - Telephone
PMHW	Manhole - Water
PMON	Monuments/statues or other related items
PMVF	<i>Miscellaneous detail features - Not at Ground</i>
POPL	<i>Obscured Pole - Aerial Surveys</i>
POPS	Obscured Post - Aerial Surveys
PPBX	Pullbox
PPHV	Horizontal Vertical Control - Aerial Surveys
PPOL	Pole
PPST	Post - all types
PPTR	Transmission line tower
PPWR	Power pole
PRJM	Project marker
PRSL	Railroad signal
PRSN	Railroad sign
PRSW	Railroad switchstand
PSGL	Traffic signal without mast arm
PSGN	Sign - Single post
PSGO	Obscured Sign - Aerial Surveys
PSIL	Sill point
PSLM	State line marker
PSND	Sign - Double post
PSOL	Obscured Traffic Signal - Aerial Surveys
PSSA	Survey traverse string
PSTK	Septic Tank
PSTP	Stump
PSTT	Storage tank fill cap
PSUM	Catch basin/Drop inlet sump
PSWP	Swamp symbol
PTCS	Tree - Coniferous
PTDS	Tree - Deciduous
PTEL	Telephone/telegraph pole
PTLM	Town line marker
PTPT	Test pit
PTRI	Tree from Aerial Mapping - Aerial Surveys
PVNT	Vent pipe - Outlet
PWEL	Well
PWGT	Water gate
PWSO	Water shutoff
QP	Pool
QS	Stockpile/lumber pile
RD	Ridge line
RM	Ramp - Boat; etc.
RO	Rock outcrop
RP	Rip-rap
RR	Railroad
RL	Retaining wall - Left ---^---^---

RW	Retaining wall - Right ---v---v---
SC	Signal conduit
SD	Loop detector
SG	Storage tanks
SK	Sidewalk
SL.....	Shore line - Left
SN	Sign - Billboard or other large sign (string feature)
SO	Stockpile
SO	Stockpile - Pit surveys
SP.....	Steps
SQ	Obscured Steps - Aerial Surveys
SR	Shore line - Right
ST.....	Intermittent or small stream
SU	Sluiceway
SW.....	Stone wall
TB	Bridge abutment - Top
TC	Curb - Top
TD	Obscured Top of Curb - Aerial Surveys
TE	Top of Curb - No Elevation Change from Bottom - Aerial Surveys
TF.....	Exposed bridge footing - Top
TH	Headwall - Top
TK	Tank - Aerial Surveys
TL	Trail
TN	Transmission Tower - Aerial Surveys
TO	Obscured Trail - Aerial Surveys
TP.....	Top of bridge pier
TR	Retaining wall - Top
TR	Retaining Walls - Aerial Surveys
TS.....	Top of slope
TS.....	Top of slope - Pit surveys
TW	Edge of traveled way
UD.....	Underdrain
UE	Underground Electric
UG.....	Underground Gas
UO.....	Obscured Utility - Aerial Surveys
US	Underground Sewer
UT	Underground Telephone
UW	Underground Water
WA	Swamp/marsh or wet area
WB	Wing wall - Bottom
WD	Delineated wetland
WF.....	Waterfall
WL	Woods line or brush line - Left
WR	Woods line or brush line - Right
WS.....	Waste - Pit surveys
WT	Wing wall - Top
X.....	Break Lines - Aerial Surveys
ZA	Intermediate contour - Approximate
ZB	Intermediate contour - Approx. depression
ZD	Intermediate contour - Depression
ZF.....	Intermediate contour - Standard

APPENDIX G – MX DESIGN STRING LABELING CONVENTION

Mainline alignment	MC-M
Side Road alignment	MC-A
Detour alignment.....	MC-B
Driveway alignment	MC-D
Preliminary alignment	MC-P
Ramp alignment	MC-R
Survey alignment.....	MC-S
Railroad alignment.....	MC-T
Road Center Line (Geometry).....	GC
Road Center Line (Proposed Elevations)	LC
Road Center Line (Old Ground Elevations).....	OC
Roadway (Edge)	CE
<i>Formerly TW</i>	
Roadway (Hard Strip)	CS
<i>Boundary between travel lane and median</i>	
Roadway (Hinge)	CH
<i>Used for line separating travel lane from widened section</i>	
Roadway (Curb Return)	CR
 Shoulders (Edge)	
<i>Formerly EP</i>	ES
Shoulders (Shoulder rollover)	ER
Shoulders (Flowline)	EF
Shoulders (Top of Curb).....	ET
Shoulders (Back of Curb).....	EB
Shoulders (Front of Sidewalk).....	EW
Shoulders (Back of Sidewalk).....	EX
Shoulders (Level Datum)	EH
<i>Top of slope, 0.3m (1') from ES string</i>	
<i>This is the string to be used as the datum string for INTERFAC macros</i>	
 Earthworks (Cut left)	IL
<i>Formerly ICL</i>	
Earthworks (Cut right)	IR
<i>Formerly ICR</i>	
Earthworks (Fill)	IF
Earthworks (Front of Ditch).....	ID
Earthworks (Back of Ditch)	IE
Earthworks (Cut Berm)	IB
Earthworks (Fill Berm)	IS
Earthworks (Widened area for 2:1 slopes)	IY
Earthworks (Top of Slope).....	IZ
Earthworks (Rounding).....	R
 Traffic Island ()	TI
Traffic Island ()	TJ
<i>Traffic Island ()</i>	TK
<i>Traffic Island ()</i>	TL
Traffic Island (Flowline)	TF
Traffic Island (Top of Curb).....	TT
Traffic Island (Back of Curb).....	TB
 Curb Return (M String).....	MR

APPENDIX H – MX DATA TRANSFER FORMATS

LANDXML

The use of LandXML is encouraged for transferring design data. LandXML was established to exchange design data utilizing a non-proprietary data standard. LandXML is the easiest avenue for transferring alignments between design softwares, including (but not limited to) MX, InRoads, and Geopak.

Survey data and surface triangulations may also be transferred via LandXML. However at this time, there are still limitations when transferring large models (surfaces). Also, all LandXML data imported to MX (except round trip data) must be mapped for each and every transfer. This can be very time consuming if working with large amounts of data. Therefore, it is strongly recommended to translate only essential data.

Importing LandXML data to MX and exporting MX data to LandXML are documented on the department's web site. Also, learn more about LandXML at www.LandXML.org.

Traditional formats used for importing alignment data to MX are also described below.

HALGN

HALGN should only be used for transferring alignment data between two groups who both use MX. LandXML should be used to transfer alignment data between different design software. HALGN is an ASCII format that can be used to define a horizontal alignment in MX using straight and circular elements.

A maximum of 500 elements may be processed.

Single element alignments may be defined.

SAMPLE HALGN INPUT DATA

```
MOSS
EDIT, PALIGN
004, 3=MC4A
004, 3=GC4A
999
HALGN, PALIGN, PALIGN
300, LB=MC4A, SC=10000.000, CF=10000.000, CE=25.000, TL=0.500
301, 1, SX, X1=1074148.120202, Y1=386094.810662, X2=1074100.198409, Y2=386000.786026
301, 2, LE, RA=150.000000
301, 3, SX, X1=1074100.198409, Y1=386000.786026, X2=1074173.873438, Y2=385776.465497
301, 4, RE, RA=150.000000
301, 5, SX, X1=1074173.873438, Y1=385776.465497, X2=1074187.614075, Y2=385623.903222
301, 6, LE, RA=150.000000
```

```

301, 7, SX, X1=1074187.614075, Y1=385623.903222, X2=1074439.853660, Y2=384526.11973
9
301, 8, RE, RA=675.000000
301, 9, SX, X1=1074439.853660, Y1=384526.119739, X2=1074076.050658, Y2=384210.19930
7
999
FINISH

```

DESCRIPTION OF HALGN FORMAT

```

MOSS .....MX files begin with this line to clear any previous errors
EDIT, PALIGN.....Tell MX to EDIT the model called PALIGN. For simplicity always
use this model name in files generated from other design packages.
004, 3=MC4M.....The 004 option tells MX to delete the string labeled MC4M if it
currently exists. MX alignments are named with 4 character labels
beginning with "MC". The third character is selected by the user and
can be any alpha-numeric character. However, the selected character
cannot be used for more than one alignment. See the Design string
labeling convention on page 63 for the appropriate fourth character.
004, 3=GC4M.....Delete the corresponding Geometry String. Use the label above
changing the initial character to "G"
999.....Tell MX to end the EDIT command
HALGN, PALIGN, PALIGN.....Begin the HALGN option. Include the model name twice.
300, LB=MC4M, SC=10000.000, CF=10000.000, CE=25.000, TL=0.500
Initiate the alignment.
LB = Alignment label
SC & CF are start station. These numbers should match
CE = Station interval. Typically 25 for Imperial projects, 10 for metric
TL is a curve tolerance, use 0.5
301, 1, SX, X1=1074148.120202, Y1=386094.810662, X2=1074100.198409, Y2=386000.78602
6
Tangent and curve sections are defined using option 301. The first
field after the 301 record is a sequence number beginning at 1. The
following code tells the type of element; SX = Tangent, LE = Left-hand
curve, RE = Right-hand curve.
X1, Y1 are coordinates at the beginning of the tangent section
X2, Y2 are coordinates at the end of the tangent section
301, 2, LE, RA=150.000000.....This line creates a left-hand curve between the tangent in the line above
and the one below with a radius of 150.
301, 3, SX, X1=1074100.198409, Y1=386000.786026, X2=1074173.873438, Y2=385776.46549
7
301, 4, RE, RA=150.000000
301, 5, SX, X1=1074173.873438, Y1=385776.465497, X2=1074187.614075, Y2=385623.90322
2
301, 6, LE, RA=150.000000
301, 7, SX, X1=1074187.614075, Y1=385623.903222, X2=1074439.853660, Y2=384526.11973
9
301, 8, RE, RA=675.000000
301, 9, SX, X1=1074439.853660, Y1=384526.119739, X2=1074076.050658, Y2=384210.19930
7
999
FINISH.....Indicates the end of input data

```

VERAT

VERAT should only be used for transferring alignment data between two groups who both use MX. LandXML should be used to transfer alignment data between different design software. VERAT is an ASCII format that can be used to define the vertical components of a previously created MX alignment.

SAMPLE VERAT INPUT DATA

```

MOSS
VERAT, PALIGN, PALIGN
MC4M, 10000.000000, 10145.714000, 7=9
10000.000000, 328.220000
10003.600000, 328.097000, 0.010000
10004.800000, 328.037000, 0.010000
10010.800000, 327.867000, 0.010000
10041.000000, 327.500000, 40.000000
10095.000000, 327.875477, 30.000000
10118.624000, 329.271000, 0.010000
10135.902000, 330.756000, 0.010000
10145.714000, 331.789000
999
FINISH
    
```

DESCRIPTION OF VERAT FORMAT

MOSS	MX files begin with this line to clear any previous errors
VERAT, PALIGN, PALIGN.....	Begin the VERAT option. Include the model name twice.
MC4M, 10000.000000, 10145.714000, 7=9	Begin the profile definition in the format: String label,start station,end station,7=number of profile points defined
10000.000000, 328.220000	Start data – Beginning station,elevation
10003.600000, 328.097000, 0.010000.....	Vertical PI point – Station 100+03.6, elevation 328.097, 0.01 curve length The 0.01 curve length is used to indicate a grade break. In this case the alignment is crossing another roadway at an intersection. Station 100+03.6 is the point where the alignment crosses the edge of travelled way on the intersecting road.
10004.800000, 328.037000, 0.010000	
10010.800000, 327.867000, 0.010000	
10041.000000, 327.500000, 40.000000	this line shows a vertical curve with a length of 40 at VPI station 100+41, elevation 327.5
10095.000000, 327.870000, 30.000000	
10118.624000, 329.271000, 0.010000	
10135.902000, 330.756000, 0.010000	
10145.714000, 331.789000	End of profile station and elevation.
999.....	Tell MX to end the VERAT command
FINISH.....	Indicates the end of input data

APPENDIX I – CONSTRUCTION REPORTS

SAMPLE ALIGNMENT REPORT (COGO STYLE)

Description of ALIGNMENT M101

```

*ELEMENT      1 TANGENT
  PBT      156+00.00          N  500908.132    E  98347.355
          DISTANCE      12.662    DIRECTION      S 49 06 45 E
  PC      156+12.66          N  500899.844    E  98356.927
*ELEMENT      2 CURVE LEFT
  PC      156+12.66          N  500899.844    E  98356.927
  PI      158+45.26          N  500747.591    E  98532.771
          RADIUS=      1909.860    DEGREE=      03 00 00
          LENGTH=      462.917    DELTA=      13 53 15
          TANGENT=      232.598    L CHORD=      461.784
          EXTERNAL=      14.112    L CH BRG=      S 56 03 22.5 E
          MID ORD=      14.008
  PT      160+75.58          N  500641.993    E  98740.017
*ELEMENT      3 TANGENT
  PT      160+75.58          N  500641.993    E  98740.017
          DISTANCE      1993.548    DIRECTION      S 63 00 00 E
  PC      180+69.13          N  499736.941    E  100516.282
*ELEMENT      4 CURVE RIGHT
  PC      180+69.13          N  499736.941    E  100516.282
  PI      182+16.20          N  499670.171    E  100647.325
          RADIUS=      2864.789    DEGREE=      02 00 00
          LENGTH=      293.889    DELTA=      05 52 40
          TANGENT=      147.073    L CHORD=      293.760
          EXTERNAL=      3.773    L CH BRG=      S 60 03 40 E
          MID ORD=      3.768
  PT      183+63.02          N  499590.333    E  100770.842
*ELEMENT      5 TANGENT
  PT      183+63.02          N  499590.333    E  100770.842
          DISTANCE      1550.624    DIRECTION      S 57 07 20 E
  PAT     199+13.64          N  498748.578    E  102073.104
    
```

SAMPLE ALIGNMENT REPORT (COORDINATES)

<u>Point</u>	<u>North</u>	<u>East</u>	<u>Elevation</u>	<u>Station</u>
1	500004.15	99991.85	636.90	70100.00
2	500008.48	99994.35	637.00	70105.00
3	500010.22	99995.36	637.04	70107.01
4	500012.81	99996.85	636.99	70110.00
5	500017.14	99999.35	636.89	70115.00
6	500021.47	100001.85	636.79	70120.00
7	500025.80	100004.35	636.69	70125.00
8	500026.69	100004.86	636.67	70126.02
9	500030.13	100006.85	636.51	70130.00
10	500034.46	100009.35	636.32	70135.00
11	500038.79	100011.85	636.13	70140.00
12	500043.12	100014.35	635.95	70145.00
13	500047.45	100016.85	635.78	70150.00
14	500051.78	100019.35	635.62	70155.00
15	500052.40	100019.71	635.60	70155.72
16	500056.11	100021.85	635.47	70160.00
17	500060.45	100024.34	635.33	70165.00
18	500064.79	100026.83	635.20	70170.00
19	500069.13	100029.31	635.08	70175.00
20	500073.47	100031.79	634.97	70180.00
21	500077.82	100034.26	634.87	70185.00
22	500082.17	100036.72	634.77	70190.00
23	500086.52	100039.18	634.69	70195.00
24	500090.88	100041.63	634.61	70200.00
25	500095.24	100044.08	634.55	70205.00
26	500099.60	100046.52	634.49	70210.00
27	500103.97	100048.95	634.44	70215.00
28	500108.34	100051.38	634.41	70220.00
29	500112.71	100053.81	634.38	70225.00
30	500117.09	100056.23	634.36	70230.00
31	500121.47	100058.64	634.35	70235.00
32	500125.85	100061.04	634.35	70240.00
33	500130.24	100063.45	634.36	70245.00
34	500134.63	100065.84	634.37	70250.00
35	500139.02	100068.23	634.40	70255.00
36	500143.42	100070.61	634.44	70260.00
37	500147.81	100072.99	634.48	70265.00
38	500152.21	100075.36	634.54	70270.00
39	500156.62	100077.73	634.60	70275.00
40	500161.03	100080.09	634.66	70280.00
41	500165.44	100082.45	634.72	70285.00
42	500169.85	100084.80	634.78	70290.00
43	500174.27	100087.14	634.84	70295.00
44	500178.69	100089.48	634.90	70300.00
45	500183.11	100091.81	634.96	70305.00
46	500187.54	100094.13	635.02	70310.00
47	500191.97	100096.45	635.08	70315.00
48	500196.40	100098.77	635.14	70320.00
49	500200.83	100101.08	635.20	70325.00
50	500205.27	100103.38	635.26	70330.00
51	500209.71	100105.68	635.32	70335.00

APPENDIX J – CROSS SECTION SET LABELS

<u>Section Set</u>	<u>Feature Name</u>	<u>MX Label</u>
0,1	Coniferous & Deciduous Trees	PTCS, PTDS
2	Environment lines	VB, VH, VO, VT, VZ, WD
3	Right-of-way lines	BC, BN, BP, BR, BS, BT
4,5	Joint Pole	PJNT
6,7	Hydrant	PHYD
8,9	Building sills	BD
A,B	Guy Pole	PGUY
C	Other	Determined by user
D	Design	Design model
E	Existing Ground	Triangulation
F	Subgrade	
G,H	Light Pole	PLIT
I,J	Joint Pole with Light	PLTJ
K,L	Power Pole with Light	PLTP
M,N	Pole	PPOL
O,P	Power Pole	PPWR
Q,R	Telephone Pole	PTEL
S	Catch Basin	PCBD
T	Drop Inlet	PDID
U	Drainage Manhole	PMHD
V	Utility Manholes	PMHE, PMHG, PMHS, PMHT, PMHW
W	Xtra Label	
X	Old Ground Elevations	OC
Y	General	
Z	Temporary	Used by MX wizards